

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-075-20241-00-00
Spot: CSENW Sec/Twnshp/Rge: 19-21S-40W
3330 feet from S Section Line, 3330 feet from E Section Line
Lease/Unit Name: WELTON Well Number: 1
County: HAMILTON Total Vertical Depth: 3187 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: PO BOX 18496 6200 N WESTERN AVE.
OKLAHOMA CITY, OK 73154

Conductor Pipe: Size feet: 8/03.58
Surface Casing: Size 8.625 feet: 350 WITH 275 SX CMT
Production: Size 5.5 feet: 3187 WITH 425 SX CMT
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 01/23/2002 11:50 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (405) 848-8000

Proposed Plugging Method: PUMP 5 SX HULLS FOR PLUG, 200 SX 60/40 POZ MIX W/6% GEL/ PRESSURE UP ON BACK-SIDE (8-5/8" X 5-1/2") & PUMP 50 SX DOWN ANNULUS IF NESCESARY.

Plugging Proposal Received By: KEVIN STRUBE WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 01/23/2002 12:50 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 2820'. PERFS AT 2779-2836'. PUMPED DOWN 5 1/2" WITH 500# HULLS & 225 SX CMT. MAXIMUM PRESSURE 1000#. SHUT IN AT 250#. PUMPED DOWN 8 5/8" X 5 1/2" ANNULUS 25 SX CMT. MAXIMUM PRESSURE 250#. SHUT IN AT 0# CIRCULATING CMT UP 8 5/8" BACKSIDE INTO CELLAR.

1-31-02
RECEIVED
JAN 31 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed Kevin D Strube
(TECHNICIAN)

INVOICED JAN 29 2002
DATE Feb 1-02
INV. NO. 2002061326