

7-2

2-070292

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER: 15.159.30211.0000  
SE, SECTION 3 TOWNSHIP 21 RANGE 9W

OPERATOR LICENSE # 5708 FEET FROM S SECTION LINE  
FEET FROM E SECTION LINE

OPERATOR Aspen Drilling  
NAME & Box 783  
ADDRESS Great Bend, KS 67530

LEASE NAME: Tobias #2  
COUNTY: Rice  
WELL TOTAL DEPTH: 3010'

97.83

CONDUCTOR PIPE: " @  
SURFACE CASING: 7" @ 257'

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SMD  D&A

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: Rockhold Engineering  
ADDRESS: Great Bend, KS LICENSE: 5111

COMPANY TO PLUG AT: HOUR: 10:00 DAY: 2 MONTH: 7 YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Bob Palaster  
COMPANY NAME: Aspen Drilling PHONE: \_\_\_\_\_

WERE: 25 sx @ 2600' - 35 sx @ 1200' - 35 sx @ 750' - 300' to surface.

PLUGGING PROPOSAL RECEIVED BY: Phil Worley

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (  ) PART (  ) NONE (  )

COMPLETED: HOUR: 2:00 DAY: 2 MONTH: 7 YEAR: 1990

ACTUAL PLUGGING REPORT:  
Pumped 25 sx to 2600' - let set 4 days - shot 4-1/2" off - pulled to 1200' - pumped 35 sx - pulled to 750' - pumped 35 sx - pulled to 300' - pumped to surface.

REMARKS: Allied #5590 60/40 4%

I DID OBSERVE THIS PLUGGING.

Jack Luthi  
Jack Luthi (AGENT)

MAILED  
JUL 12 1990  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

FORM CP-2/3  
REV. 3/90

DATE 7-24-90

INV. NO. 28696

Mk