

5 060172

6-19 15.159.00428.0000 <sup>109</sup>

R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- drilled 10-5-60  
SE SE SW, SEC. 33, T 21 S, R 9 W/EX  
330 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6332

Lease Name Wellman Well # I #1

Operator: Kenbill Oil Co.

County Rice 114.89

Name & Address Box 1647

Well Total Depth 3535 feet

Great Bend, KS 67530

~~XXXXXX~~ Pipe: Size 5-1/2" feet 3530/125 SX

Surface Casing: Size 8-5/8 feet 221

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9:00a Day: 19 Month: 6 Year: 19 89

Plugging proposal received from Clay Duntz

(company name) Kelso Casing Pulling (phone) 316-938-2943

were: Sand to 2985' - cap w/5 sx cement - pull pipe to 1150' - 35 sx thru 5-1/2"  
pipe - pull pipe to 700' - 35 sx thru 5-1/2" pipe - pull pipe to 300' - circ  
cement to surface

JUN 26 1989

CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by \_\_\_\_\_ District #2  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:45a Day: 19 Month: 6 Year: 19 89

ACTUAL PLUGGING REPORT Sanded to 2985' - capped w/5 sx cement- pulled 5-1/2" pipe  
to 1150' - 35 sx cement - pulled 5-1/2" to 700' - 35 sx cement - pulled pipe to  
280' - circ 100 sx cement to surface.

Perf 3470-77' - 3078-81' - 3044-46' - 3038-40' - Rec. 1600' of 5-1/2"

Remarks: Allied #522 Used 60/40 poz 2% gel

(if additional description is necessary, use BACK of this form.)

I (did / ~~xxxxxxx~~) observe this plugging.

DATE 7-3-89

Signed R. Phil Worley  
(TECHNICIAN)

INV. NO. 25140