

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

McPherson County, Sec. 34 Twp. 21 Rge. (E) 3 32W

Location as "NE/CNW/SW" or footage from lines SE SW NW

Lease Owner The Henderson Oil Company

Lease Name Neufeldt Well No. 1

Office Address 335 Union Center, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed 3-21 1957

Application for plugging filed 3-21 1957

Application for plugging approved 3-21 1957

Plugging commenced 3-21 1957

Plugging completed 3-22 1957

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ruel E. Durkee

Producing formation Depth to top Bottom Total Depth of Well 3522 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		cemented		8 5/8	240	w/200 sacks

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy mud to 240'  
Set plug at 240' ~~fix~~  
Poured 15 sacks thru drill pipe  
Filled with heavy mud to 15'  
Set #2 plug at 15'  
Filled with cement to top, cut pipe off below surface

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Drilling Company  
Address Box 786, El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.  
O N Wilson - contractor (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) O N Wilson  
El Dorado, Ks (Address)

SUBSCRIBED AND SWORN TO before me this 25th day of March, 1957

My commission expires November 27, 1958 Notary Public.

PLUGGING  
FILE SEC 34 T. 21 R. 3W  
BOOK PAGE 1 LINE 34

MAR 26 1957  
CONSERVATION DIVISION  
Wichita, Kansas

3-26-57

**WELL LOG**

15.113.30235.0000

Operator The Henderson Oil Company  
 Comm 3-9-57 Comp 3-21-57  
 Shot        Qts. From        ft. To        ft.  
 Acidized        Gal.  
 Prod. Formation Dry & Abandoned  
 Initial Prod.         
 Elevation       

Lease Neufeldt Well No. 1  
 Loc. SE SW NW Sec 34 Twp 21S Rge 3W  
 County McPherson State Kansas  
 Contractor Red Drilling Company

		Casing Record		
	Size	Ft.	Pulled	Remarks
cemented	8 5/8	240'		

FIGURES INDICATE BOTTOM OF FORMATION

30 surface soil & clay  
 170 sand  
 180 red bed  
 249 shale blue  
 980 shale & shells  
 1220 lime & shale  
 1500 shale  
 2312 lime & shale  
 2365 sandy shale  
 2640 lime & shale  
 2764 lime  
 2955 lime & shale  
 3020 lime  
 3169 lime & shale  
 3256 lime  
 3280 lime & chert  
 3370 lime  
 3493 shale  
 3522 lime & shale  
 Total Depth 3522'

RECEIVED  
 STATE COMMISSION

PLUGGING  
 FILE SEC 34 T 21 R 3W  
 BOOK PAGE 1 LINE 34

CONSE  
 Wichita