

TIGHT

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
1000 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-075-20567-0000

LEASE NAME Daniel Morgan

WELL NUMBER 1-13

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

2310 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 13 TWP. 21S RGE. 39 (E) (W)

COUNTY Hamilton

Date Well Completed 9-6-95

Plugging Commenced 9-6-95

Plugging Completed 9-6-95

LEASE OPERATOR Amoco Production Company

ADDRESS PO Box 800 Room 924 Denver, CO 80201

PHONE (303) 830-5323 OPERATORS LICENSE NO. 5952

Character of Well _____

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on September 6, 1995 (date)

BY Steve Pfifer (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? ACO-1 and logs are being sent in at the same time as this report.

Producing Formation Dry Depth to Top _____ Bottom T.O.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface			8.625"	392'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

This well was plugged using 60/40 POZw/ 6% Gel and # Flocel as follows: Plug No 1-2325' w 50 sx cement; Plug No 2-1200' w/ 80 sx cement; Plug No 3-600' w 30 sx cement; Plug No 4-420' w 50 sx cement; Plug No 5-40' w 10sx cement; Rathole w 15 sx cement; Mousehole w 10 sx cement. Cut off casing and capped well.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton

RECEIVED
KANSAS CORPORATION COMMISSION

Address _____

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Amoco Production Company SEP 18 1995

STATE OF Colorado COUNTY OF Denver

CONSERVATION DIVISION
WICHITA, KS

Samuel J. Carmack (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Samuel J. Carmack

(Address) 2225 West Oklahoma Ulysses, KS

SUBSCRIBED AND SWORN TO before me this 13th day of September, 1995

Donna J. Monroe
Notary Public

My Commission Expires: May 4, 1999