

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-159-21,252-0000

LEASE NAME Gullick Estate #1

WELL NUMBER _____

SPOT LOCATION S/2 SE SE

SEC. 7 TWP. 21 RGE. 8 (E) or (W)

COUNTY Rice

Date Well Completed _____

Plugging Commenced 12/26/84

Plugging Completed 1/2/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Sterling Drilling Co.

ADDRESS Box 129, 6th & Cleveland, Sterling, Ks. 67579

PHONE # (316) 278-2131 OPERATORS LICENSE NO. _____

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Salina

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3530'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	216'	none
				5 1/2"	3521'	2536'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 3250' & 5 sacks cement. Shot pipe at 2734', & 2536'. Pulled 60 joints of pipe. Plugged well with 5 hulls, 20 gel, 8 5/8 plug, & 100 sacks poz 2% gel 3% c.c.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss. RECEIVED STATE CORPORATION COMMISSION

R. Darrell Kelso (employee of operator) or JAN 10 1985
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God. CONSERVATION DIVISION
Wichita, Kansas

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 8th day of January, 1985

My Commission expires: _____



Irene Hoover
Notary Public

15-159.21252-0000

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- GULLICK ESTATE #1-7
Located: 660' FEL; 330' FSL, SE/4, Section 7-218-8W,
Rice County, Kansas

OWNER: Sterling Drilling Company, et al
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: August 1, 1981

COMPLETED: August 8, 1981

TOTAL DEPTH: 3530'

LOG

CASING RECORD

0 - 227 Sand and Shale
(185 - 227) Plug and Cement
227 - 1000 Shale
1000 - 3175 Lime and Shale
3175 - 3530 Lime

Ran 6 joints new 8 5/8" OD casing.
212.37" pipe set at 223.87' K.B.
Cemented with 225 sacks 60/40 Pozmix with
2% gel and 3% cc. Plug down at 2:15 PM,
8-1-81, by Howco.

Ran 86 joints new 5 1/2", 14#, 8rd,
Range 3 OD casing. 3512.38' pipe set
at 3521.38' K.B. Cemented with 150
sacks 50/50 Pozmix, with 2% gel, 3/4
of 1% CFR-2 and 18% salt. 20 bbls. salt
flush ahead of cement. Plug down at
8:45 PM, 8-8-81, by Howco.

RECEIVED
STATE CORPORATION COMMISSION

SEP 25 1984

CONSERVATION DIVISION
Wichita, Kansas

Deviation Survey: 2° at 3154'