


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

McPherson County, Sec. 27 Twp. 21 Rge. 2W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SE/4 NW/4 NE/4 (1560' FSL & 1120' FWL NE/4)

Lease Owner John J. Darrah
Lease Name Schrag Well No. 1
Office Address 1010 Century Plaza Bldg., Wichita, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole) 67202
Dry Hole



Locate well correctly on above
Section Plat

Date Well completed August 15, 1979
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 19
Plugging completed August 15, 1979
Reason for abandonment of well or producing formation
Dry Hole

If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman, Holyrood, Ks.
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Clay		0	30'	8 5/8"	30'	None
Sand		30'	85'	8 5/8"	55'	None
Shale		85'	135'	8 5/8"	50'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set bottom plug at 130' with 20 sacks of cement. Top plug set at 40' with 10 sacks of cement, 2 sacks in rathole. Plugging completed at 5:00 A. M., August 15, 1979. State Plugger, Gilbert Toman, Holyrood, Kansas.

8-22-79
STATE RECEIVED
AUG 22 1979

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Blackstone Drilling, Inc., Box 1184, McPherson, Kansas 67460

STATE OF Kansas COUNTY OF Sedgwick, ss.
John J. Darrah (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John J. Darrah
1010 Century Plaza Bldg., Wichita, Ks. 67202
(Address)

SUBSCRIBED AND SWORN TO before me this Aug. day of 17, 1979

My commission expires May 2, 1982
Jeanne C. Kepner Notary Public.





Blackstone Drilling, Inc.

Box 1184 • 523 West Kansas • Phone (316) 241-1260
McPHERSON, KANSAS 67460

August 16, 1979

COMPANY: JOHN J. DARRAH
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: SCHRAG #1
 LOCATION: (1560' FSL & 1120' FWL NE/4)
 SE NW NE Section 27-21-2W,
 McPherson County, Kansas
 COMMENCED: August 8, 1979
 COMPLETED: August 15, 1979
 ELEVATION: 1486 K. B.

0	to	30	Clay
30	to	85	Sand
85	to	700	Shale
700	to	1120	Shale & Lime
1120	to	1530	Shale
1530	to	1900	Shale & Lime
1900	to	2130	Lime & Shale
2130	to	2180	Sand
2180	to	2317	Shale & Lime
2317	to	2430	Lansing
2430	to	3009	Lime
3000	to	3009	Shale & Lime
3009	to	3300	Mississippi
3300	to	3305	Kinderhook
3305	to	3398	Shale & Lime
		3398	T. D.

Cut 12 1/4" hole to 131' and run 133' of 8 5/8" surface casing, cemented with 100 sacks of cement at 131'. Plug down at 9:30 A. M., August 8, 1979. Cut 7 7/8" hole to 3398'. Set bottom plug at 130' with 20 sacks of cement. Top plug cemented with 10 sacks at 40'. 2 sacks in rathole. Hole plugged at 5:00 A. M., August 15, 1979 by State Plugger, Gilbert Toman, Holyrood, Kansas.

TOPSE LANSING - 2430' MISSISSIPPI - 3009'

Measurements taken from K. B.

CERTIFICATE

I, P. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Schrag #1, located on the SE/4 NW/4 NE/4 Section 27-21-2W, McPherson County, Kansas as reflected by the files of Blackstone Drilling, Inc.


P. E. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 16th day of August, 1979.


Johnnie L. Schmidt - Notary Public

