

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

McPherson

County. Sec. 27 Twp. 21 Rge. 2W (E) (W)

Location as "NE/CNW/SW" or footage from lines N/2 NE NE

Lease Owner John J. Darrah

Lease Name Moundridge Townsite Well No. 1

Office Address 1010 Century Plaza Bldg., Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed August 18, 1978

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced 19

Plugging completed August 18, 1978

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Clay		0	25'	10 3/4"	25'	None
Sand		25'	35'	"	10'	None
Blue Shale		35'	80'	"	45'	None
Shale		80	133'	"	53'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set bottom plug at 125' with 30 sacks of cement. Set top plug at 30' with 18 sacks of cement, 2 sacks in rathole. Plug down at 6:15 A. M., August 18, 1978. Plugging completed by State Plugger, Gilbert Toman, Holyrood, Kansas.

8-24-1978

RECEIVED
STATE CORPORATION COMMISSION

AUG 24 1978

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Blackstone Drilling, Inc.

Address P.O. Box 1184, McPherson, Kansas 67460

STATE OF Kansas, COUNTY OF Sedgwick, ss.

John J. Darrah

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature)

1010 Century Plaza Bldg., Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of August, 1978

Jeanne C. Kepner
Jeanne C. Kepner Notary Public.

My commission expires





Blackstone Drilling, Inc.

Box 1184 523 West Kansas • Phone (316) 241-1250
McPHERSON, KANSAS 67460

August 18, 1978

COMPANY: JOHN J. DARRAH
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: MOUNDRIDGE TOWNSITE #1
 LOCATION: N/2 NE NE 1/4, Section 27-21-2W,
 McPherson County, Kansas
 COMMENCED: August 10, 1978
 COMPLETED: August 18, 1978
 ELEVATION: 1482 K. B.

0	to	25	Clay
25	to	35	Sand
35	to	80	Blue Shale
80	to	133	Shale
133	to	720	Shale & Lime
720	to	1550	Lime & Shale
1550	to	1840	Shale
1840	to	2341	Shale & Lime
2341	to	2365	Lansing
2365	to	2545	Lime
2545	to	2727	Lime & Shale
2727	to	2880	Lime
2880	to	2995	Lime & Shale
2995	to	3005	Shale & Lime
3005	to	3116	Mississippi
3116	to	3290	Lime
3290	to	3371	Kinderhook
3371	to	3397	Lime & Shale
		3397	T. D.

Cut 15 1/4" hole to 131' and run 133' of 10 3/4" surface pipe, cemented with 100 sacks of cement (2% Gal & 2% cc) at 131'. Plug down at 11:00 A. M., August 10, 1978. Cut 8 3/4" hole to 3397'. Hole dry and abandoned. Set bottom plug at 125' with 30 sacks of cement, Set top plug at 30' with 18 sacks of cement, 2 sacks of cement in rathole. Plugging completed at 6:15 A. M., August 18, 1978 by Gilbert Toman, State Plugger, Holyrood, Kansas.

Tops:

Measurements taken from K. B.

CERTIFICATE

I, P. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Moundridge Townsite #1 located on the N/2 NE NE 1/4, Section 27-21-2W, McPherson County, Kansas as reflected by the files of Blackstone Drilling, Inc.


P. E. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 18th day of August, 1978.


Johnnie L. Schmidt - Notary Public

