

REC'D FEB 25 1959

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

McPherson County, Sec. 27 Twp. 21 Rge. 2 (E) W (W)

Location as "NE/CNW/SE/SW" or footage from lines NW NW NE

Lease Owner Brunson-Spines, Inc.

Lease Name Krehbiel "G" #1 Well No.

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 2-21-59 19

Plugging completed 2-23-59 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toaman

Producing formation Depth to top Bottom Total Depth of Well 3396 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	240'	none
				5-1/2"	3395'	2823'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked the hole to 3395' and found it open. Filled w/sand to 3385' and dumped 5 sacks of cement with bailer. Pulled 5 1/2" casing, cleared hole and mudded to 240', set rock bridge to 230' and dumped 20 sacks of cement. Mudded the hole to 30', set rock bridge and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETED

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.

Address Chase, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss. I, Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight

Chase, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 24th day of February, 19 59

9-27-62

Thomas V. Rogers

Notary Public.

My commission expires

RECEIVED  
STATE CORPORATION COMMISSION

MAR 14 1959

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 27 T 21 R 2W  
BOOK PAGE 15 LINE 16

BRUNSON-SPINES  
Wichita, Kansas

WELL: KREHBIEL "G" #1

NW NW NE

COMMENCED RD: 9-19-58

27-21S-2W

COMPLETED RD: 9-28-58

McPHERSON COUNTY, KANSAS

TOTAL DEPTH: 3395' - 75' *pat*

ELEVATION: 1482 KB

CASING: 240' 8-5/8" - 150' *pat*

CONTRACTOR: BRUNSON PROD. &amp; EXPLOR.

STRATA	DEPTH	TOPS	
Surface Soil & Clay	25	Lansing	2356 (-874)
Sand & Gravel	80	Sooy Shaly Congl.	2975 (-1493)
Shale & Shells	325	Mississippi	3008 (-1526)
Lime & Shale	2457	Kinderhook	3264 (-1782)
Sandy Lime	2482	Hunton	3376 (-1894)
Lime & Shale	2837	Maquoketa	3388 (-1906)
Lime	3015	Total Depth	3395 (-1913)
Lime & Chert	3266		
Lime	3302		
Shale	3377		
Lime & Shale	3380		
Lime	3395 T.D.		

**RECEIVED**  
STATE PETITION COMMISSION  
FEB 14 1959  
STATE PETITION DIVISION  
WICHITA, KANSAS

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling report.

BRUNSON-SPINES

*Ralph B. McLaughlin*  
Ralph B. McLaughlin

Signed and sworn to in my presence this 30th day of October, 1958, by Ralph B. McLaughlin, of Brunson-Spines.

*Mary G. LaFollette*  
Mary G. LaFollette, Notary Public

My commission expires June 16, 1959.

<b>PLUGGING</b>	
FILE SEC. 27 T. 21 R. 2W	
BOOK PAGE 15 LINE 16	