


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Rice County. Sec. 27 Twp. 21S Rge. 10W(E) (W)  
Location as "NE/CNW/SW" or footage from lines NE SW NE  
Lease Owner Thunderbird Drilling Company, Inc.  
Lease Name Fair "D" Well No. 1  
Office Address 712 Union Center, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) D & A  
Date well completed March 20 19 63  
Application for plugging filed March 20 19 63  
Application for plugging approved March 20 19 63  
Plugging commenced March 20 19 63  
Plugging completed March 20 19 63  
Reason for abandonment of well or producing formation D & A



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert J. Toman  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3490 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	245	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Fill hole w/heavy mud to 235',  
plug & 20 sx common cement. Fill  
hole w/heavy mud to 35' 1/2 sx hulls  
plug & 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

APR 8 1963

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling Co.  
Address Box 173--Russell, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
George A. Angle (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George A. Angle  
580 Fourth Natl. Bank Bldg., Wichita, Ks.  
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of March, 19 63

My commission expires 11-17-66

Dorothy L. Head  
Notary Public.

INVOICED

DATE 4/8/63

INV. NO. 6859-11

DRILLERS LOG

Fair "D" #1

CASING RECORD: 8 5/8" @ 245' w/225 sx cement  
 COMPANY: Thunderbird Drilling Co.  
 CONTRACTOR: Red Tiger Drilling Co.  
 COMMENCED: March 13, 1963  
 COMPLETED: March 20, 1963  
 DESCRIPTION: NE SW NE 27-21S-10W Rice County, Ks.  
 ELEVATION: 1726 GR 1731 RB  
 TOTAL DEPTH: 3490'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand	0	100	
Sand & Shale	100	245	
Shale	245	365	
Anhydrite	365	385	
Shale	385	700	
Shale & Shells	700	1300	
Shale Shells & Lime	1300	1545	
Shale & Lime	1545	1670	
Lime	1670	1775	
Lime & Shale	1775	2921	
Lime	2921	3490	

RECEIVED  
 STATE CORPORATION COMMISSION  
 APR 8 1963  
 CONSERVATION DIVISION  
 Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

*George A. Angle*  
 George A. Angle

Subscribed and sworn to before me this 22nd day of March, 1963.

*Doraine V. Head*  
 Notary Public

My Commission Expires:

11-17-66