

WELL PLUGGING RECORD
K.A.R.-82-3-117

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. MARKET, ROOM 2078
WICHITA, KS 67202

RECEIVED
NOV 13 2001
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out Completely
and return to coms. div.
office within 30 days.

API NUMBER 15-145-21465 - 00-00
LEASE NAME Kasselmann
WELL NUMBER 2
2970 ft. from S Section Line
660 ft. from E Section Line
SEC. 14 TWP. 23 RGE. 16 (E) or (W)
COUNTY Pawnee

LEASE OPERATOR Pintail Petroleum
ADDRESS 225 N. Market, Wichita, KS 67202
PHONE # (319) 263-2243 OPERATORS LICENSE NO. 5086
Character of well oil

Date Well Completed _____
Plugging Commenced 10/26/01
Plugging Completed 10/29/01

(Oil, Gas, D&A, SWD, input, Water Supply Well)
The plugging proposal was approved on 10/26/01 (date)
by Steve Durant (XCC District Agent's Name).

Is ACO-1 filed? yes if not, Is well log attached? not available to us

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4128

Show depth and thickness of all water, oil and gas formations

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	261	none
				4 1/2	4142	1840

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set

Sand at 3987, baled 4 sacks cement. Shot pipe at 2837, 2244, 2004, 1840. Pulled to 1000, pumped 15 sacks gel, 50 sacks cement. Pulled to 290, pumped 50 sacks cement. Pulled to 40', pumped 10 sacks cement. Layed last jt. down.

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925
Address 401 West Main, Lyons, KS 67554

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Pintail Petroleum Co.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Walter I. Phillips, Jr. (Employee of Operator) or (Operator) of above - described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above - described well as filled that the same are true and correct, so help me God.


(Signature) Walter Phillips Jr

(Address) 225 N. Market, #300, Wichita, KS

SUBSCRIBED AND SWORN TO before me 12th day of November, 2001

Patricia C. Byerlee
Notary Public

My commission Expires: 12/11/2001



Form CP-4
Revised 05-88

OR

ALLIED CEMENTING CO., INC.

7332

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Ness City

DATE <u>10-29-01</u>	SEC. <u>14</u>	TWP. <u>23</u>	RANGE <u>16 W</u>	CALLED OUT <u>11:00am</u>	ON LOCATION <u>12:00noon</u>	JOB START <u>1:00pm</u>	JOB FINISH <u>3:30pm</u>
LEASE <u>Kasselman</u>	WELL# <u>2</u>	LOCATION <u>Zook-3 East - 1/4 South</u>			COUNTY <u>Dawnee</u>	STATE <u>KS</u>	
<u>OLD</u> OR NEW (Circle one)			<u>West into</u>				

CONTRACTOR Quality Well Service

TYPE OF JOB _____

HOLE SIZE _____ T.D. _____

CASING SIZE _____ DEPTH _____

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

OWNER Pintail Pet.

CEMENT

AMOUNT ORDERED 110 sx 60/40 6% gel
10 gel on side

COMMON	<u>66</u>	@	<u>6.65</u>	<u>438.90</u>
POZMIX	<u>44</u>	@	<u>3.55</u>	<u>156.20</u>
GEL	<u>10</u>	@	<u>10.00</u>	<u>100.00</u>
CHLORIDE		@		
		@		
		@		
		@		
		@		
HANDLING	<u>126</u>	@	<u>1.10</u>	<u>138.60</u>
MILEAGE	<u>42</u>			<u>211.68</u>

EQUIPMENT

PUMP TRUCK CEMENTER Jack

224 HELPER Tim Lee

BULK TRUCK

_____ DRIVER LARRY H.

BULK TRUCK

_____ DRIVER _____

RECEIVED

NOV 13 2001

KCC WICHITA SERVICE

TOTAL \$ 1105.38

REMARKS:

1st plug @ 1000' with 8 gel - 50 sx cement - 2 gel

2nd plug @ 250' with 50 sx cement

Top off @ 40' with 10 sx cement

Hole stayed full

— Thanks —

DEPTH OF JOB	<u>1000'</u>			
PUMP TRUCK CHARGE				<u>475.00</u>
EXTRA FOOTAGE		@		
MILEAGE	<u>42</u>	@	<u>3.00</u>	<u>126.00</u>
PLUG		@		
		@		
		@		

TOTAL \$ 601.00

CHARGE TO: Pintail Pet.

STREET 225 North Market

CITY Wichita STATE KS ZIP 67202

FLOAT EQUIPMENT

	@		
	@		
	@		
	@		
	@		

TOTAL _____

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX \$ 83.61

TOTAL CHARGE \$ 1789.99

DISCOUNT \$ 170.64 IF PAID IN 30 DAYS

SIGNATURE Richard O. McJannet

PRINTED NAME

Net \$ 1619.35