

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

WELL PLUGGING RECORD

15-145-21096-0000

Give All Information Completely
 Make Required Affidavit

COUNTY Pawnee SEC. 18 TWP. 23S RGE. 16W EAW
 Location as in quarters or footage from lines:
 NE SE SW

Locate Well
 correctly on above
 Section Platt.

Lease Owner F. G. Holl
 Lease Name Frick Well No. 1-18
 Office Address 6427 East Kellogg, Wichita, Kansas 67207
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed December 1, 1983
 Application for plugging filed December 1, 1983
 Plugging commenced 6:00 AM, December 1, 1983
 Plugging completed 8:45AM, December 1, 1983
 Reason for abandonment of well or producing formation
Dry Hole

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthie
 Producing formation _____ Depth to top _____ bottom _____ T.D. 4310'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	415'	None

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Filled hole with heavy mud,
 Plugged through open ended drill pipe 50 sacks at 1060';
 50 sacks at 520', 1/2 sack hulls, plug and 10 sacks
 at 40'. 15 sacks in rathole with joint of pipe.
 5 sacks in water well. Used 60/40 Pozmix, plus
 2% gel (total 4%) and 3% cc.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor STERLING DRILLING COMPANY, P. O. Box 129, Sterling, Ks. 67579

STATE OF KANSAS COUNTY OF RICE, ss.

F. A. Wuellner (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

STERLING DRILLING COMPANY
 (Signature) F. A. Wuellner
F. A. Wuellner, Secretary
 (Address)
 P. O. Box 129, Sterling, Kansas 67579

SUBSCRIBED AND SWORN TO before me this 2nd day of December, 1983.



4-6-85

Agnes D. Wurst, Notary Public.

STATE CORPORATION COMMISSION

DEC 7 1983
 CONSERVATION DIVISION
 Wichita, Kansas

12-7-83

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

15-145-21096-0000

WELL LOG - - - - - FRICK #1-18

Located: NE SE SW, Section 18-23S-16W, Pawnee County,
Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: November 21, 1983

COMPLETED: December 1, 1983

TOTAL DEPTH: 4310'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 80 Surface Soil and Sand	Ran 10 joints new 8 5/8", 24# casing. 403.37' set at 415' K.B.
80 - 180 Shale	Cemented with 325 sacks 60/40 Pozmix, 3% cc. Plug down at 7:15 PM, 11-21-83, by Howco.
180 - 418 Shale and Red Bed	
418 - 1060 Shale, Sand and Red Beds	
1060 - 1079 Anhydrite	
1079 - 1985 Shale	
1985 - 4310 Lime and Shale	Plugged.

Deviation Surveys: 1° at 2225'
1° at 4310'