

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

15-145-20766-0000

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Pawnee County, Sec. 18 Twp. 23 Rge. 16 E/W

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
C SE NW NW

Lease Owner Stalcup Oil Co.

Lease Name Frick Well No. 1

Office Address 3511 - 23rd, Great Bend, Kansas 67530

Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole

Date Well completed Dec. 22 19 80

Application for plugging filed Dec. 22 19 80

Application for plugging approved Dec. 22 19 80

Plugging commenced Dec. 22 19 80

Plugging completed Dec. 22 19 80

Reason for abandonment of well or producing formation Dry Hole


If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4200

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE   | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8 5/8" | 310    |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

- First plug @ 660' w/70 sacks cement
- Second plug @ 270' w/25 sacks cement
- Solid bridge plug @ 40' w/10 sacks cement
- 5 sacks cement in rat hole
- 50/50 Pozmix, 4% Gel,

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Mustang Drilling & Exploration, Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.  
Milford Martin (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God?

(Signature) Milford Martin  
Box 1425, Great Bend, Kansas 67530  
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of December, 19 80

BEVERLY SHEWBART  
Notary Public  
Barton County, Kansas  
April 24, 1982

Beverly Shewbart  
Notary Public.

STATE CORPORATION COMMISSION

DEC 20 1980

CONSERVATION DIVISION  
Wichita, Kansas

My commission expires

DRILLERS' WELL LOG

15-145-20766-0000

DATE COMMENCED: December 16, 1980  
 DATE COMPLETED: December 22, 1980

Stalcup Oil Co.  
 "FRICK # 1"  
 C SE NW NW  
 Sec 18-T23-R16  
 Pawnee County, Kansas

ELEVATION: 2069 K.B.

0 - 314' Surface Clay, Blue Shale  
 314 - 1064' Red Bed, Shale  
 1064 - 1083' Anhydrite  
 1083 - 2000' Shale  
 2000 - 2510' Shale, Lime  
 2510 - 3070' Lime, Shale  
 3070 - 3290' Shale, Lime  
 3290 - 3700' Lime, Shale  
 3700 - 3974' Lime  
 3974 - 4066' Lime, Shale  
 4066 - 4084' Lime  
 4084 - 4136' Shale, Chert  
 4136 - 4200' Lime  
 4200' RTD

FORMATION TOPS (Log)  
 Herrington/Krider 2095  
 Winfield 2152  
 Towonda 2218  
 Iatan 3700  
 Lansing 3708  
 Kansas City 3751  
 Base K.C. 3974  
 Fort Scott 4066  
 Cherokee 4084  
 Kinderhook 4099  
 Chattanooga 4112  
 Viola 4136  
 RTD 4200  
 Log TD 4202

SURFACE PIPE:  
 Set used 8 5/8", 24' pipe @ 310'  
 w/275 sacks Common, 2% Gel, 3% cc.

A F F I D A V I T

STATE OF KANSAS )  
 COUNTY OF BARTON ) ss.

I, Milford Martin, of Mustang Drilling & Exploration, Inc. do state that the above is true and correct to the best of my knowledge.

*Milford Martin*  
 \_\_\_\_\_  
 Milford Martin

Subscribed and sworn to before me this 23rd day of December, 1980/

*Beverly Shewbart*  
 \_\_\_\_\_  
 Notary Public

NOTARY PUBLIC  
 BEVERLY SHEWBART  
 Barton County, Kansas  
 My Appointment expires April 14, 1982

My Appointment expires April 14, 1982

DEC 29 1980

REGISTRATION DIVISION  
 Wichita, Kansas