


WELL PLUGGING RECORD

15-145-20082-0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Pawnee County, Sec. 18 Twp. 23S Rge. 16W (E) 16W
Location as "NE/CNWxSWx" or footage from lines C S 1/2 N 1/2 SW SW

Lease Owner Messman-Rinehart Oil Company

Lease Name MIELKE UNIT Well No. 1

Office Address 1432 Wichita Plaza - Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 10-22 19 68

Application for plugging filed 10-22 19 68

Application for plugging approved 10-22 19 68

Plugging commenced 10-22 19 68

Plugging completed 10-22 19 68

Reason for abandonment of well or producing formation No oil or gas found
in commercial quantities.

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4250 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	317'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud. Pumped 100 sacks 50-50 Pozmix, 6% gel, and 100# hulls down surface pipe. Completed at 11:45 AM 10-22-68.

RECEIVED
STATE CORPORATION COMMISSION
NOV 5 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co., Inc.

Address 1425 Wichita Plaza - Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Wilson Rains (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains
Wilson Rains
1425 Wichita Plaza - Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 25 day of October 19 68

My commission expires June 30, 1971

Sherry Gish
Sherry Gish Notary Public.

15-145-20082-0000

ROTARY DRILLING LOG

Operator: Messman-Rinehart
Oil Company
MIELKE UNIT #1
C S $\frac{1}{2}$ N $\frac{1}{2}$ SW SW 18-23S-16W
Pawnee County, Kansas

Contractor: Rains & Williamson
Oil Co., Inc.
Commenced: 10-13-68
Completed: 10-22-68
Casing: 8-5/8" @ 317'/200 sx.

Formations:

Surface soil and Sand	60'
Shale	320'
Shale and Shells	1062'
Anhydrite	1082'
Shale and Shells	1960'
Shale and Lime	2170'
Lime and Shale	2585'
Shale and Lime	3455'
Lime and Shale	3920'
Lime	4200'
Lime and Chert	4250'
Rotary Total Depth (D & A)	4250'


RECEIVED
STATE CORPORATION COMMISSION
NOV 5 1968
CONSERVATION DIVISION
Wichita, Kansas

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO., INC.


Wilson Rains

Subscribed and sworn to before me, a Notary Public within and for the State of Kansas, County of Sedgwick, this 25th day of October, 1968.


Sherry Gish Notary Public

My Commission Expires;
June 30, 1971