

STATE OF KANSAS
STATE CORPORATION COMMISSION


15-145-20360-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pawnee County, Sec. 19 Twp. 23 Rge. 16 E/W
Location as "NE/CNW/SW $\frac{1}{4}$ " or footage from lines
SW NW SW

Lease Owner National Oil Company
Lease Name Thomas #1 Well No. _____
Office Address 3 Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above Section Plat

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 9/12/78 _____ 19____
Plugging completed 10/ 9/78 _____ 19____
Reason for abandonment of well or producing formation depleted. _____

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4254
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	308	none
				4 $\frac{1}{2}$ "	4254	2455'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Squeezed bottom hole with 35 sacks and pumped plug to 3900'. Shot pipe at 3430', 3243', 3104', 2964', 2824', 2680', 2540', pulled 68 joints. Squeezed hole with 3 sacks hulls, 25 sacks gel, released plug and displaced with 150 sacks 50-50 pozmix 2% gel.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

OCT 16 1978

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor KELSO CASING PULLING CONSERVATION DIVISION
CHASE, KANSAS Wichita, Kansas

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of October, 19 78

My commission expires _____



Margaret Melcher
Notary Public.

K. T. WOODMAN
RES. PHONE 733-0418
OFF. PHONE 265-7650
WICHITA, KANSAS

D. J. IANNITTI
PHONE 792-2921
GREAT BEND, KANSAS

WOODMAN & IANNITTI DRILLING COMPANY

Rotary Drilling Contractors

1008 UNION NATIONAL BUILDING
WICHITA, KANSAS 67202

15-145-20360-0000

February 25, 1975

Company;	National Oil Company
Farm;	#1 Thomas
Location;	SW NW SW
Section;	19-23S-16W
County;	Pawnee
Contractor;	Woodman & Iannitti Drilling Company
Comm;	February 13, 1975
Compl;	February 24, 1975
Total Depth;	4255
Casing;	8 5/8" @ 308 w/200 sacks 4 1/2" @ 4254 w/150 sacks

Figures Indicate Bottom Of Formations:

60	Clay & Sand
190	Red Shale
308	Blue Shale
375	Shale
560	Red Bed & Shale
620	Sand
700	Shale
1065	Red Bed
1086	Anhy
1856	Shale & Shells
1980	Shale
2285	Lime
2765	Lime & Shale
3155	Lime & Shale
3280	Lime & Shale
3650	Lime
3840	Lime & Shale
4000	Lime
4160	Lime
4198	Lime
4255	Lime

RECEIVED
STATE CORPORATION COMMISSION

AUG 07 1978

CLERK OF COURSE
WICHITA, KANSAS

I certify the above to be a true and correct copy of the driller's log to the best of my knowledge and belief.

Woodman & Iannitti Drilling Co.

K. T. Woodman

K. T. Woodman