

WELL PLUGGING RECORD

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging of formations.

Barton County. Sec. 22 Twp 16S Rge 12 ~~XX~~ W (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE $\frac{1}{4}$ NE $\frac{1}{4}$ SW $\frac{1}{4}$
Lease Owner The Vickers Petroleum Co., Inc.
Lease Name Dolechek Well No. 2
Office Address 201 W-K-H Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed October 27 19.48
Application for plugging filed October 27 19.48
Application for plugging approved October 27 19.48
Plugging commenced October 27 19.48
Plugging completed October 27 19.48
Reason for abandonment of well or producing formation.....

NORTH

Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production.....19.....
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced?.....yes
Name of Conservation Agent who supervised plugging of this well C. D. Stough, Great Bend, Kansas
Producing formation Arbuckle Depth to top 3393 Bottom 3405 Total Depth of Well 3405 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface		0	300'	8-5/8"	300'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

Set plug at 200'. Dump 10 sx cement on plug. Set plug @ 20' and filled to bottom of cellar w/cement.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to The Vickers Petroleum Co., Inc.
Address 201 W-K-H Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
John M. Little (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John M. Little
201 W-K-H Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 2nd day of November, 1948

Allen J. Denton
Notary Public.

My commission expires August 13, 1949

PLUGGING
FILE SECT 66 (6112)
BOOK PAGE 66 LINE 1

15-009-06556-00-00

THE VICKERS PETROLEUM CO., INC.

Dolecheck Well #2
SE NE SW Sec. 22-16S-12W
Barton County, Kansas

Casing Record:
8-5/8" @ 300' w/140 sx

Commenced: October 16, 1948
Completed: October 27, 1948

Elevation: 1925 R.B.
D & A

LOG

Surface	0-255
Shale & Lime Rock	255-302
Shale	302-475
Shale & Sand	475-500
Shale & Shells	500-565
Red Bed	565-685
Red Bed & Shale	685-815
Anhydrite	815-840
Shale & Shells	840-940
Shale	940-1170
Salt & Shale	1170-1460
Shale & Lime	1460-1490
Lime Broken	1490-1825
Lime & Sand	1825-1855
Sand & Lime	1855-1890
Lime Broken	1890-2045
Lime & Shale	2045-2760
Lime	2760-3048
Shale & Sand	3048-3104
Lime	3104-3361
Lime & Shale	3361-3381
Sand & Shale Red	3381-3393
Dolomite, Weathered	3393-3400
Dolomite Solid	3400-3405 T.D.
Tops:	
Brown Lansing	3104
White Lansing	3117
Conglomerate	3381
Arbuckle	3393

I hereby certify that this log is true and correct to the best of my knowledge and belief.

THE VICKERS PETROLEUM CO., INC.

By H. C. Paris

Subscribed and sworn to before me
this 7 day of November, 1948.

Allen P. Denton
Notary Public

My commission expires August 13, 1949.

PLUGGING
 CASE SET BY 6/11/48
 LOG PAGE 66 LINE 1