


15-009-20951-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission
245 North Water
Wichita, KS 67202

FORM CP-4

WELL PLUGGING RECORD



Locate well correctly on above
Section Plot

Barton County. Sec. 22 Twp. 16S Rge. 12W (W) (V)
Location as "NE/CNW/SW" or footage from lines. C-N/2 N/2 SW/4
Lease Owner Jayhawk Oil Company
Lease Name Dolechek Well No. 1
Office Address 240 Sutton Place, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 1, 1976
Application for plugging filed Verbal Application 19 76
Application for plugging approved Verbal Approved 19 76
Plugging commenced June 1, 1976
Plugging completed June 1, 1976
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3,381 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
STATE CORPORATION COMMISSION				8 5/8"	248'	none
JUN 14 1976						
CONSERVATION DIVISION Wichita, Kansas						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 3,381 feet (Rotary Total Depth) to 420 feet. Set plug at 420 feet and cemented with 50 sxs cement. Filled hole with heavy rotary mud from 420 feet to 240 feet. Set plug at 240 feet and cemented with 25 sxs cement. Filled hole with heavy rotary mud from 240 feet to 40 feet. Set solid plug at 40 feet and cemented to cellar with 10 sxs cement, 2 sxs cement in rat hole.


Name of Plugging Contractor Allied Cementing Co., INC.
Address Box 31, Russell, Kansas 67665

STATE OF Kansas COUNTY OF Sedgwick, ss.
Dean Britting - Agent (employee of owner) or (owner or operator) of the above-described

well being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
200 North Main Wichita, KS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of June, 19 76
Elsie Willison
Elsie Willison Notary Public.
My commission expires June 30, 1978



COMPANY **Jayhawk Oil Company**

SEC. 22 T. 16S R. 12W
 LOC. C-N/2 N/2 SW/4


FARM **Dolechek**

NO. **1**

TOTAL DEPTH **3,381'**
 COMM. **May 25, 1976**
 SHOT OR TREATED
 CONTRACTOR **H-30, INC.**
 ISSUED **June 8, 1976**

COMP. **June 2, 1976**

COUNTY **Barton**
 KANSAS



CASING

20	10	
15	8	5/8" 248' cemented w/160 sxs cement
12	6	
13	5	

ELEVATION **1925 KB**

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Shale and Lime	250'
Shale and Red Bed	815'
Anhydrite	840'
Shale	1,125'
Shale and Lime	1,632'
Lime and Shale	1,860'
Shale and Lime	1,982'
Lime and Shale	2,260'
Shale and Lime	2,515'
Lime and Shale	2,695'
Shale and Lime	2,775'
Lime and Shale	2,985'
Shale and Lime	3,090'
Lime and Shale	3,175'
Lime	3,260'
Shale and Lime	3,306'
Lime	3,381'
Total Rotary Depth	3,381'

RECEIVED
 STATE COOPERATION COMMISSION

JUN 14 1976

CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Dean Britting
 Dean Britting

State Of Kansas }
 County Of Sedgwick } SS:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 8th day of June, 1976.

Elsie Willison
 Elsie Willison-Notary Public

My Commission Expires:
 June 30, 1978

