


15-009-03342-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
P. O. BOX 17027  
WICHITA, KANSAS 67217

FORM CP-4

## WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Barton County, Sec. 23 Twp. 16 Rge. 12W (E) (W)  
Location as "NE/CNW&SW" or footage from lines C N/2 SE NE  
Lease Owner. Gulf Oil Corporation  
Lease Name. Minnie #2 Well No.  
Office Address. Oklahoma City, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 8/9/75 19  
Plugging completed 8/26/75 19  
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Rankin  
Producing formation Depth to top Bottom Total Depth of Well 3370 Feet  
Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

## CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	390	none
				5 1/2"	3347	1820'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole, ran sand to 3300' and dumped 5 sacks cement on bottom.  
Shot pipe at 2609', 2415', 2230', 2135', 2036', 1935', 1836', pulled 57 joints. Plugged well with 3 sacks hulls, 15 sacks gel and 100 sacks 50-50 pos, 6% gel.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING  
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE  
R. DARRELL KELSO

(employee of owner) or (owner) or (operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

CHASE, KANSAS

(Address)

Subscribed and sworn to before me this 27th day of August, 1975

My commission expires



Notary Public.

RECEIVED  
CONSERVATION COMMISSION

AUG 28 1975

CONSERVATION DIVISION  
Wichita, Kansas

WELL NO. 2 LEASE Minnie COMPANY Gulf Oil Corporation A.F.E. 3454

DATE—DRILLING BEGAN 10-23-43 WELL COMPLETED 11-18-43 FIRST PRODUCTION 11-15-43

SAND RECORD      Arbuckle Lime      3347'      -      3370'      TOTAL DEPTH 3370'

INITIAL PRODUCTION OIL: 912 barrels on drawdown test with Echometer  
WATER: None

Corrected Gravity: 42.5  
(12-27-43)

### CASING RECORD

[illegible]

(\*) "F," FLOWING NATURALLY; "L," AIR GAS LIFT; "S," SWABBING; "P," PUMPING.

S-23 T-16S R-12W

C		
N/2		
SE		o
NE		

Barton County,  
Kansas

ELEVATION— 1918' DF  
RT 4-1/2' above 5-1/2" csg.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 18 1975

CONSERVATION DIVISION  
Wichita, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

JUL 18 1975

CONSERVATION DIVISION  
Wichita, Kansas

0 - 37' Sand and frost rock  
50 Rock  
85 Shale  
200 Shale and shells  
245 Hard sand and gravel  
300 Shale and red rocks  
390 Shale and red beds  
470 Shale and shells  
575 Red bed, sand and shale  
670 Red bed  
790 Red rock  
825 Anhydrite  
1190 Shale and shells  
1380 Salt, shale and shells  
1545 Shale and shells  
1585 Lime  
1645 Lime and shale  
1670 Lime  
1745 Shale and shells  
1775 Lime  
1790 Lime and shale  
1800 Sandy lime and shale  
1835 Lime, sand and iron  
1920 Lime and shale  
1950 Lime and streaks of iron pyrite  
2000 Lime, shale and shells  
2210 Lime and shale  
2290 Shale and shells  
2375 Shale  
2455 Shale and lime  
2470 Shale and shells  
2484 Lime  
2502 Shale and shells  
2554 Lime  
2670 Shale and lime shells  
2705 shale and shells  
2924 Lime  
2934 Sand  
2980 Lime  
3070 Shale & Kansas City Lime  
3300 Lime  
3347 Lime, Conglomerate  
3370 Arbuckle Lime (Total Depth)

JW