


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Barton County. Sec. 23 Twp. 16S Rge. 4E 12 (W)
Location as "NE/CNW/SW" or footage from lines. C SW NW NE
Lease Owner Gulf Oil Corporation
Lease Name Minnie Well No. 5
Office Address Box 661, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 2-6 1946
Application for plugging filed 10-22 1957
Application for plugging approved 10-25 1957
Plugging commenced 11-10 1957
Plugging completed 11-14 1957
Reason for abandonment of well or producing formation. Well operating below its economic limit.
If a producing well is abandoned, date of last production 7-12 1957
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Truan
Producing formation Arbuckle Depth to top 3349' Bottom 3361' Total Depth of Well 3361 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	566'	0
				5-1/2"	3350'	2161'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with sand to 3340' and spotted 5 sacks cement. Filled hole with mud to 300'. Set rock bridge and spotted 25 sacks cement. Filled hole with mud to 40'. Set rock bridge and capped with 10 sacks cement, filling hole into cellar.

NOTE: W. C. Bunch - Special Petty Cash, Check No. 1868, dated 11-21-57, in the amount of \$33.61 is attached as payment of Plugging Assessment.

RECEIVED
STATE CORPORATION COMMISSION
NOV 27 1957
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Morgan Well Plugging Service
Address 102 W. 18th Street, Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Thomas A. Trax (employee of owner) ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Box 2233, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of November, 1957

My commission expires 6-3-61 2-4-59

Ray W. Rouser
RAY W. ROUSER, NOTARY PUBLIC Notary Public.

JRM:PF

PLUGGING
FILE SEC 23 T. 16 R. 12W
BOOK PAGE 56 LINE 34

15-009-03345-00-00
 GULF OIL CORPORATION

MINNIE NO. 5

CENTER SW NW NE OF SECTION 23-16S-12W
 Barton County, Kansas

8-5/8" O.D. casing cemented at 568' Drilling commenced 1-20-46
 5-1/2" O.D. casing cemented at 3351' Drilling completed 2-4-46

FROM	TO	FORMATION	REMARKS
0'	90'	Surface sand & clay	8-5/8" O.D. casing cemented at 568'.
90	568	Shale and shells	
568	815	Red bed, shale and shells	
815	1135	Shale and shells	
1135	1424	Shale, shells & salt	
1424	1525	Shale & shells	
1525	1580	Shale & lime	
1580	1670	Lime	
1670	1855	Shale & lime shells	
1855	1950	Lime & shale	
1950	2015	Lime	
2015	2210	Lime & shale	
2210	2280	Shale	
2280	2405	Shale & shells	
2405	2530	Shale & lime	
2530	2655	Lime & shale	
2655	2725	Shale & lime	
2725	2810	Lime, broken	
2810	3078	Lime	
3078	3107	Shale	5-1/2" O.D. casing cemented with 100 sacks bulk cement at 3351'.
3107	3352	Lime	
3352	3356	Arbuckle lime	
3356	3361	Sand	
T.D.	3361'		

OCT 25 1946
 GULF OIL CORPORATION
 BARTON COUNTY, KANSAS

PLUGGING
 111 SEC 23 T 16 12W
 BOOK PAGE 56 LINE 34