

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH

Locate well correctly on above
Section Plat

BARTON

County. Sec. 23 Twp. 16 Rge. 12 (E) (W)

Location as "NE/CNW&SW" or footage from lines SW NW SW

Lease Owner COMMERCIAL OIL INC.

Lease Name REIMANN Well No. 3

Office Address 5252 N. Broadway Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 12/2/70 19

Plugging completed 12/7/70 19

Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well DON TRUAN

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2		270

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sand to 3075 dump 5 sax cement
shoot at 490 - 270 pull 270 feet.
Allied Cement pump 3 sax hulls 20 sax gel and 90 sax cement.

RECEIVED
STATE CORPORATION COMMISSION
MAR 11 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Ralph Comstock Pipe Pulling, Inc. #490
Address 320 N. Park Stafford, Kansas

STATE OF Kansas, COUNTY OF Stafford, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ralph Comstock
Stafford, Mo.
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of March, 1971
My commission expires Feb. 5, 1975
NOTARY PUBLIC
C. RICHARDSON

Lawrence C. Richardson
Notary Public.

15-009-03348-00-00
WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

COPY

Company W. L. HARTMAN
Farm Reimann


No. 3

SEC. 23
SW NW SW

T. 16 R. 12W

Total Depth. 3378'
Comm. 4-8-48 Comp. 5-19-48
Shot or Treated. Acid. w/500 gallons
Contractor.
Issued. 7-17-48

County. Barton
KANSAS



CASING:
8-5/8" 190'
5-1/2" 3373'

Elevation. _____

Production. Minimum Well

Figures Indicate Bottom of Formations.

shale & sand	0-197
shale & shells	700
shale	714
anhydrite	734
shale & shells	1735
shale & lime	2000
lime	2105
shale	2230
lime & shale	2375
shale & shells	2575
shale	2730
lime & shale	2817
lime	3378
Total Depth	

Tops: (D.F.)
Topeka 2680
Lansing-K.C. 3099
"Sooy" Conglomerate 3363
Arbuckle 3368

Rotary Total Depth 3372

200' fillup in 12 hours.

RECEIVED
STATE CORPORATION COMMISSION
DEC 4 - 1970
CONSERVATION DIVISION
Wichita, Kansas