

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

15-009-03350-00-00

Form CP-4

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 23 Twp. 16 Rge. 12 (E) (W)
Location as "NE/CNW/SW" or footage from lines c w/2 nw sw
Lease Owner ~~Reiman~~ Commercial Oil Co.
Lease Name Reiman Well No. 6
Office Address 5252 N. Broadway Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 19
Application for plugging filed 8-14- 1970
Application for plugging approved 8-14- 1970
Plugging commenced 8-15- 1970
Plugging completed 8-19- 1970
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Don Truan
Producing formation Depth to top Bottom Total Depth of Well 3374 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				4"		193

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Push plug to 3000 ft.-sand back from 3000 to 2975 ft.- dump 5
sax cement - pull 193 ft. 4" pipe.
Allied Cementing Co. pumped 3 sax hulls, 15 sax gel & 90 sax c
cement in 8" casing.

RECEIVED
STATE CORPORATION COMMISSION
OCT 7 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Ralph Comstock Pipe Pulling, Inc. Permit # 490
Address Stafford, Kansas

STATE OF Kansas, COUNTY OF Stafford, ss.
Ralph Comstock (employee of owner) or (owner or operator) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ralph Comstock
Stafford, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 2 day of Oct, 1970

My commission expires Nov 30 1970 Bryan J. Goral Notary Public.

15-009-03350-00-00

COPY

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, KansasCompany - W. L. HARTMAN
Farm - Riemann

No. 6

SEC. 23 T. 16
CW/2 NW SW

R 12W

Total Depth. 3374 R.B.

Comm. 11-30-49

Comp. 1-9-50


Shot or Treated.

Contractor. H & H Drilling Co.

Issued. 3-4-50

County. Barton

KANSAS



CASING:

8 5/8" 148' cem. w/125 sx.
5 1/2" 3368' cem. w/50 sx.

Elevation. 1928' DF

Production. 580 bbls oil/24 hrs.

Figures Indicate Bottom of Formations.

clay yllw	40
shale	345
shale & sand	530
red bed	811
anhyd.	840
shale	870
shale & sand	1485
shale & shells	1715
shale	1795
lime & shale	2088
lime	2190
shale	2240
shale & lime	2415
lime	2573
shale & lime	2820
lime	2998
shale & lime	3060
lime	3364
congl	3368
Arbuckle	3374
Total Depth R.B.	

Tops: Rotary bushing meas.

Topoka lime	2883
Heebner shale	3027
Brown lime	3095
White lime	3117
Base K.C.	3307
Congl	3363
Arbuckle lime	3367

Geological data:

D.S.T. # 1 3120-3146 weak blow first seven minutes, open 30 minutes, rec. 5' mud, very slightly oil cut. B.H.P. 0#

D.S.T. # 2 3193-3201 open 1 hr., weak blow, rec. 45' salt wtr. B.H.P. 900#

RECEIVED

STATE CORPORATION COMMISSION

AUG 14 1970

CONSERVATION DIVISION
Wichita, Kansas490
720.20 Paris
67598