

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH

Locate well correctly on above
Section Plat

Barton County, Sec. 23 Twp. 16 Rge. 12W (E) (W)
Location as "NE/CNW&SW" or footage from lines CN/2 SW NW
Lease Owner Bennett & Roberts Drilling Co.
Lease Name Reimann "B" Well No. 1
Office Address Russell, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed 7/31 19 54
Application for plugging filed 8/12 19 54
Application for plugging approved 8/13/54 19
Plugging commenced 8/14 19 54
Plugging completed 8/16 19 54
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Red Horner
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3394 1/2 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				293'	8 5/8"	None
				5 1/8"	3379 1/2'	2897'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with crushed rock to 3380',
dumped 5 sx cmt, top of cmt, 3345'. Filled
hole with mud to 290', set rock bridge,
dumped 20 sax cmt, top of cement, 230'.
Filled with mud to 35', set rock bridge,
dumped 10 sax for cap.

STATE CORPORATION COMMISSION
AUG 27 1954
8-21-54
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Miller Casing Pulling Co.
Address Great Bend, Ks.

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
Harold Wurst (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Wurst
Russell, Ks.
(Address)

SUBSCRIBED AND SWORN to before me this 19th day of August, 19 54
Anna Linnard
Notary Public.

PLUGGING
FILED 8/23/54
PAGE 56 OF 18

Bennett & Roberts Drilling Co.
Reimann "B" #1

NE SW NW Sec. 23-16-12W
Barton County, Kansas

R.T.D. 3380 1/2

Tops:

Comm: 7/21/54
Comp: 7/31/54

Set 8 5/8" @ 293' w/175 sx cmt.
Set 5 1/2" @ 3379 1/2 w/75 sx cmt.

Cimexron Anhyd.	825
Topoka Lime	2713- 770
Heebner Shale	3018-1085
Toronto Lime	3036-1103
Douglas Shale	3048-1115
Douglas Sand	3062-1129
Brown Lime	3110-1177
Lansing K.C.	3129-1196
Base K.C.	3347-1414
Arbuckle	3379-1446

<u>Formation:</u>	<u>Depth:</u>
Surface Clay & Sand	90'
Shale & Sand	225
Shale	293
Shale & Shells	440
Sand	500
Salt	590
Red Bed	825
Anhydrite	855
Shale & Shells	1500
Shale & Lime	1910
Lime	1990
Shale & Lime	2825
Lime	2879
Lime & Shale	3166
Lime	3192
Lime & Shale	3292
Lime	3380 1/2

STATE OF KANSAS)
RUSSELL COUNTY) SS.

I hereby certify that the above information is correct to the best
of my knowledge.

BECKETT & ROBERTS DRILLING CO.

Jim Lake

Subscribed and sworn to before me this 3rd day of August, 1954.

Clara Chausse
Notary Public

My Commission Expires 6/18/58

PLUGGING
 FILE SEC 23-16-R12W
 BOOK PAGE 56 LINE 18

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 13 1954