


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

15-009-15805-00-00
WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Barton County, Sec. 23 Twp. 16 Rge. 12 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SE NE NW
Lease Owner The Henderson Oil Company
Lease Name Reimann Well No. 2
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 1-26-61 _____ 19____
Plugging completed 1-28-61 _____ 19____
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Don Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3369 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	200'	None
				5-1/2"	3359'	651'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3359', ran 20 gal. of sand to 3340' and dumped 5 sacks of cement @ 3340' with dump bailer. Pulled 5 1/2" casing, parted @ 650'. Ran bailer to 210', drilled bridge to 260', set 10' rock bridge to 250' and ran 30 sacks of cement. Mudded to 40' set 10' rock bridge to 30' and ran 10' sacks of cement to base of cellar.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

FEB 5 1961

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of January, 1961

My commission expires May 20, 1964 Milton J. Volin Notary Public.

15-009-15805-00-00

THE CARL TODD DRILLING COMPANY
404 KFH Building
Wichita 2, Kansas

The Carl Todd Drilling Company, et al
RIEMANN No. 2
SE NE NW 23-16S-12W
Barton County, Kansas

Date Commenced: October 10, 1951
Date Completed: October 23, 1951

Casing Record:

8-5/8" casing cemented at 200'
with 125 sacks cement.

Elevation: 1923' D.F.
1925' R.B.

5-1/2" casing cemented at 3359'
with 100 sacks cement.

Rotary Tools: 0' to 3362'
Cable Tools: 3362' to 3369' T.D.

LOG

FORMATION TOPS - R.B.

0	75	Surface clay, rock
75	250	Shale, shells
250	350	Shale, red bed
350	530	Shale, sand
530	815	Shale, shells
815	835	Anhydrite
835	900	Shale, red bed
900	1190	Shale, shells
1190	1345	Shale, salt
1345	1530	Shale, shells
1530	1670	Shale, lime
1670	1735	Lime
1735	2765	Lime, shale
2765	2970	Lime
2970	3087	Shale, lime
3087	3155	Lime
3155	3185	Lime, shale
3185	3358	Lime
3358	3362	Sand, Rotary Total Depth
3362	3369	Sooy Sand, Total Depth

Topeka	2674
Heebner	2994
Brown Lansing	3086
Sooy Sand	3358

RECEIVED
STATE COMMISSION COMMISSION

JAN 18 1961

CONSERVATION DIVISION
Wichita, Kansas

Swabbed 34.6 barrels oil in 12 hours, trace of water.
Putting on pump.

I, Carl Todd, do hereby certify that
the above log is correct to the best
of my knowledge and belief.

Carl Todd