


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavits
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plot

Stafford County, Sec. 17 Twp. 21S Rge. (E) 12W (W)
Location as "NE/CNW/SW" or footage from lines SW NW SE
Lease Owner Circle Oil Company, Inc.
Lease Name WESTAFER Well No. 1
Office Address 500 Bitting Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 3, 19 66
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced May 3, 19 66
Plugging completed May 3, 19 66
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Archie Elving)

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 3630 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	273	8-5/8"	4/26/66	
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud from Total Depth to 260 Feet;
Hull Plug & HOWCO Plug and 25 sacks cement
through the Drill Pipe; Mud to 40 feet;
1/2 sack Halls and Plug bridged and 10 sacks
cement to Base of Cellar; 2 sacks in Rat Hole.
Job completed at 6:30 A.M.

RECEIVED
STATE CORPORATION COMMISSION
MAY 9 - 1966
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sage Drilling Co., Inc.
Address 500 Bitting Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Thomas M. McCaul, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature)

500 Bitting Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of May, 19 66

My commission expires November 26, 1966.
Louise K. Whitted - Notary Public.

DRILLERS LOGWESTAFER NO. 1

CASING RECORD:	COMPANY: Circle Oil Co.	DESCRIPTION:
8-5/8" @ 273' w/225 sax cement	CONTRACTOR: Sage Drilling Co.	SW NW SE Sec. 17-21S-12W Stafford County, Kansas
TOTAL DEPTH: 3630'	COMMENCED: April 26, 1966	ELEVATION: 1866 KB
	COMPLETED: May 3, 1966	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	275	
Sand & Shale	275	1223	Anhydrite top not picked; estimated at 678.
Shale & Shells	1223	1525	
Sandy Lime & Shale	1525	1725	
Lime & Shale	1725	2420	
Shale w/Lime Streaks	2420	2860	
Lime & Shale	2860	3005	
Shale & Lime	3005	3195	
Lime & Shale	3195	3426	
Lime	3426	3441	
Lime & Shale	3441	3630	

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 9 - 1966
 CONSERVATION DIVISION
 Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING COMPANY, INC.

By

Thomas M. McCaul, Jr.
Thomas M. McCaul, Jr.

Subscribed and sworn to before me this 5th day of May, 1966.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1966.