

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

OR

FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plugging  
of formations.

Stafford County. Sec 17 Typ 21 Rge. 12 (E) (W)

Location as "NE1/4NW1/4SW1/4" or footage from lines NE1/4 NE1/4 NE1/4

Lease Owner Geo. F. Johnston, Jr.

Lease Name Lucy B. Westafer Well No. B1

Office Address 304 Orpheum Bldg.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed December 23 1948

Application for plugging filed December 22 1948

Application for plugging approved December 22 1948


Plugging commenced December 23 1948

Plugging completed December 23 1948

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above  
Section Plat

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation Depth to top Bottom Total Depth of Well 3532 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	342	
				4 1/2	3480	3047

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud. Set plug at 200 ft.

Mixed and pumped 15 sacks cement on plug.

Filled hole with heavy mud to 30 ft. Set plug at 20 ft.

Mixed and pumped 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Geo. F. Johnston Jr.  
Address 304 Orpheum Building, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick ss.  
Geo. F. Johnston, Jr. (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Geo. F. Johnston, Jr.  
304 Orpheum Building  
(Address)

SUBSCRIBED AND SWORN to before me this 30th day of December 1948

My commission expires March 22, 1952

22-2626

2-48-15M



GEO. JOHNSTON  
Orpheum Building  
Wichita, Kansas

Westafer #1

NE NE NE  
Section 17-21S-12W  
Stafford County, Kansas

Commenced RD: 11/15/48  
Completed RD: 11/27/48  
Total Depth: 3495'

Elevation: 1852'  
Initial Prod: D & A  
Drilling Contractor: Brunson Drilling  
Co., Inc.  
Tools: Rotary

Casing: 335' 8-5/8"  
3480' 4-1/2" OD

STRATA	DEPTH		
Sand	125		
Shells & sand	260		
Sand	300		
Blue shale	310		
Shale & shells	335		
Shale	350		
Red bed	655	TOPS -	From Derrick Floor
Anhydrite	680		
Shale & red bed	810	Brown Line	3209
Shale & shells	900	Kansas City	3226
Shale	1090	Conglomerate	3446
Shale & shells	1160	Simpson	3461
Salt & shells	1375	Arbuckle	3478
Shale & shells	1605	Arbuckle	3490 Show Oil-170'
Lime	1650	Total Depth	3534
Shale & lime	1860		
Lime	2040	Acid - 2000 Gals. at	3490'
Shale & lime	2975		
Lime	3495		
Total Depth	3495		

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling reports.

BRUNSON DRILLING COMPANY, Inc.  
By

*William S. Brunson*  
Wm. S. Brunson Sec.

Signed and sworn to in my presence this 6th day of December, 1948, by Wm. S. Brunson, secretary of the Brunson Drilling Company, Inc., a corporation in the State of Kansas

*Jan C. Detweiler*  
Notary Public

My commission expires September 10, 1951.

