

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Stafford County. Sec. 17 Twp. 21 Rge. 12 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW NE SW

Lease Owner Fred B. Anschutz

Lease Name Heaton Well No. 3

Office Address 709 Union Nat'l Bk Bldg., Wichita, Kans.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 3-31 19 50

Application for plugging filed 3-31 19 50

Application for plugging approved 3-31 19 50

Plugging commenced 3-31 19 50

Plugging completed 3-31 19 50

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation Depth to top Bottom Total Depth of Well 3620 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	319	-
						4-5-50
					APR 5 1950	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pushed first wooden plug to 319', mixed and poured 15 sacks cement through drill pipe; second wooden plug to 30' and poured 10 sacks cement

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Anschutz Drilling Company, Inc.
Address 709 Union Nat'l Bk Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

H. R. Jensen (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. R. Jensen

709 Union Nat'l Bk Bldg., Wichita, Kans.


(Address)

SUBSCRIBED AND SWORN to before me this 4th day of April, 19 50.

Martha Boyce
Notary Public.

My commission expires September 12, 1953

22-7877-8 4-40-10M



FRED B. ANSCHUTZ

Heaton #3, SW NE SW 17-21-12
Stafford County, Kansas

COMMENCED: 3-20-50
COMPLETED: 3-31-50

0	250	Sand
250	295	Sand and red bed
295	345	Red Bed
345	675	Red bed & shells
675	700	Anhydrite
700	790	Shale and shells
790	1170	Shale and shells
1170	1300	Shale and shells
1300	1410	Shale and salt
1410	1535	Broken lime and shale
1535	1665	Lime and shale
1665	1760	Lime
1760	1825	Shale and shells
1825	1860	Lime
1860	1970	Lime and shale
1970	2035	Broken lime and shale
2035	2145	Shale and shells
2145	2275	Shale and lime
2275	2410	Shale and lime
2410	2545	Shale and shells
2545	2660	Shale and lime
2660	2770	Shale and lime
2770	2895	Shale and lime
2895	2975	Lime
2975	3045	Lime
3045	3115	Lime
3115	3180	Lime
3180	3265	Shale and lime
3265	3272	Shale
3272	3320	Lansing lime
3320	3375	Lime
3375	3430	Lime
3430	3485	Lime
3485	3537	Lime and shale
3537	3585	Conglomerate
3585	3620	Conglomerate
3620		Rotary Total Depth

CASING RECORD
Set 8-5/8" surface casing
at 319' with 200 sacks
cement.

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I hereby affirm that the above and foregoing is a true and correct copy of the log of the #3 Heaton located SW NE SW of Section 17-21-12, Stafford County, Kansas.

ANSCHUTZ DRILLING COMPANY, INC.

By: *A. R. Jensen*

Subscribed and sworn to before me this 4th day of April, 1950.

Martha D. Jones
Notary Public

My commission expires September 12, 1953

PLUGGING
FILE SEC 17-21-R-12W
BOOK PAGE 146 LINE 4