


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Stafford County, Sec. 17 Twp. 21 Rge. 12 (E) W (W)

Location as "NE/CNW\*SW\*" or footage from lines SW SE SW  
Lease Owner Great Bend Pipe & Supply Co., Inc.  
Lease Name Heaton Well No. 5  
Office Address Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 3-14-63 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 3-17-63 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well H. Justus  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3588 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	329'	None
				5-1/2"	3536'	2887'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to 3588', sanded to 3530' and dumped 5 sacks of cement @ 3530' with dump bailer. Pulled 5 1/2" casing, checked fluid to 60', bailed fluid to 200', set rock bridge to 190' and ran 20 sacks of cement @ 190'. Mudded hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 28 1963

CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY  
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.  
Noel J. Knight (employee of owner) or (~~OWNER~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 22nd day of March, 1963

My commission expires May 20, 1964

Milton J. Volin  
Notary Public.



Longhand Record.

15.185.12658.0000

ANSCHUTZ PROD.

J5 Hester

SW SE SW 17-21-12W

Stafford County, Kansas

EL: 1862 FB  
1860 DF  
1858 GR

Contractors Rig #2

4-18-50 Moving in  
 4-19 9-5/8" cog. @ 329'  
 200 mm & 2 CC  
 4-21 Dig 1600'  
 4-22 Dig 2000'  
 4-24 2780  
 4-25 3090  
 4-26 3365  
 4-27 3479  
 4-28 TD 3510 = 3530 BLC  
 5/2 3536 1/2

Topoka 2895 (-973)  
 Hoebner 3117 (-1895)  
 Brw Ls 3223 (-1305)  
 Lane 3263 (-1101)  
 ARB 3535 (-1673) Corr

5-6 Moving in spudder  
 5-8 drilled shoe, had only slight show of oil  
 to test and deepen  
 5-9 deepened 2' T.D. 3512  
 7' in Arbuckle - scrubbed 1/2 BOPW all night, preparing to  
 acidize w/1000 gal.  
 5-10 Acidized w/1000 gal. 100' max pressure. Scrubbed load  
 back & scrubbed 17 BOPW first hr, settled to 10 BOPW in  
 1/2 hr. Re-acidized 3/1000 gal, scrubbed load back, did  
 not get back all the acid water. Now making 6 1/2 Bbls  
 per hour with 1% acid water. Will continue to scrub.  
 5-11 Scrubbed 7 1/2 BOPW/5 hrs off bottom, cleaned out to T.D.  
 Running tubing & rods  
 5-12 Finished running tubing and rods, tore down. Building pumping  
 unit aside.  
 5-13 Load line and gas line in, waiting on spudder to move off.  
 5-15 To set pumping unit as soon as spudder moves off  
 5-17 Ready to pump - waiting on post rock to take State Test  
 5-19 Taking physical State Test today  
 5-22 State Test 157 BOPD no water