


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Stafford County. Sec. 17 Twp. 21S Rge. 12W (E) (W)
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines NW NE SW
Lease Owner Fred B. Anschutz
Lease Name Heaton
Office Address 709 Union National Bank Bldg., Wichita, Ks.
Well No. 7
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 3/12 19 51
Application for plugging filed 3/13 19 51
Application for plugging approved 3/13 19 51
Plugging commenced 3/13 19 51
Plugging completed 3/13 19 51
Reason for abandonment of well or producing formation Dry
If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Flat

Name of Conservation Agent who supervised plugging of this well C. D. Stough, Great Bend, Kansas
Producing formation Depth to top Bottom Total Depth of Well 3615 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	321'	----

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set Bottom plug @ 300' with 15 sacks cement
Set top plug @ 30' with 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
3-23-51 MAR 23 1951
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Anschutz Drilling Company
Address 709 Union National Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
H. R. Jensen (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. R. Jensen
709 Union National Bank Bldg., Wichita (Address)

SUBSCRIBED AND SWORN to before me this 22nd day of March 1951

Patricia Meeker
Patricia Meeker Notary Public

My commission expires Jan. 21, 1954.

PLUGGING
FILE SEC 17 T 21 S R 12 W
BOOK PAGE 27 LINE 10

DRILLER'S LOG
 #7 Heaton
 NW NE SW * Section 17-21S-12W
 Stafford County, Kansas

0	341	Sand & Red rock
321	665	Red bed & shells
665	690	Anhydrite
690	710	Shale & shells
710	1090	Shale & shells
1090	1170	Shale & shells
1170	1225	Shale & salt
1225	1450	Shale & shells
1450	1480	Shale & shells
1480	1605	Lime
1605	1730	Lime
1730	1855	Shale & lime
1855	2000	Lime & Shale
2000	2105	Lime & shale
2105	2220	Lime & shale
2220	2390	Shale & lime
2390	2540	Shale & lime
2540	2625	Lime & shale
2625	2915	Shale & lime
2915	2960	Lime
2960	3120	Lime
3120	3180	Lime & shale
3180	3252	Shale
3252	3305	Lime
3305	3370	Lime
3370	3425	Lime
3425	3470	Lime
3470	3520	Lime
3520	3556	Conglomerate
3556	3581	Lime
3581	3610	Shale & chert
3610	3615	Shale
3615		RTD

COMMENCED: 3/1/51
 COMPLETED: 3/13/51

TOPS:

Anhy. 665
 Heeb. 3116 (-1249)
 B. L. 3249
 Lans. 3264
 Cong.
 RTD 3615 in Cong.

CASING RECORD:

Set 8-5/8" surface
 csg. @ 321' w/225 Sacks

D & A

COUNTY OF SEDGWICK)
) SS.
 STATE OF KANSAS (

I hereby affirm that the above and foregoing is a true and correct copy of the log of the #7 Heaton located in the NW NE SW of Section 17-21S-12W, Stafford County, Kansas.

ANSCHUTZ DRILLING COMPANY, INC.

BY: *M. W. Smith*
 M. W. Smith

Subscribed and sworn to before me this 22nd day of March, 1951.

Patricia Decker
 Notary Public

My commission expires January 21, 1954.

RECORDED
 COMMISSION COMMISSIONER
 MAR 23 1951
 COUNTY CLERK'S DIVISION
 WICHITA, KANSAS

PLUGGING
 FILE SEC-17-21S-12W
 BOOK PAGE-67, LINE 10