


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Stafford County, Sec. 17 Twp. 21S Rge. (E) 12 (W) SW NW NW
Location as "NE/CNW/SW" or footage from lines _____
Lease Owner Aspen Resources, Ltd.
Lease Name Goodman Well No. 1
Office Address P. O. Box 783, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oilwell
Date well completed February 12 1970
Application for plugging filed December 22 1970
Application for plugging approved December 23 1970
Plugging commenced March 6 1971
Plugging completed March 23 1971
Reason for abandonment of well or producing formation not economical to produce



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production December 15 1970
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well G. Russell Biberstein
Producing formation Lansing-Kansas City depth to top 3244 Bottom _____ Total Depth of Well 3625 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	3624'	2735'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Made bottom hole plug back with sand to 3200', mixed and ran 5 sacks cement thru dump bailer.
Mixed and pumped 3 sacks bulls, 15 sacks mud and 100 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
MAR 30 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pawnee Drilling Co., Inc.
Address P. O. Box 783, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Robert L. Pelster (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 26th day of March, 19 71

My commission expires April 18, 1972

Theora Holleman
Theora Holleman
Notary Public.

DRILLERS LOG

COMPANY: Aspen Resources, Ltd.
 CONTRACTOR: Aspen Drilling Co.
 LEASE NAME: Goodman #1
 LOCATION: SW-NW-NW Sec. 17-T21S-R12W
 Stafford County, Kansas
 ELEVATION: 1860 KB
 SURFACE CASING: 7 jts. (282') 8 5/8"
 OIL STRING: 117 jts. (3631') 5 1/2"
 COMMENCED: December 30, 1969
 COMPLETED: January 11, 1970
 ROTARY TOTAL DEPTH: 3625'

FORMATION	DEPTH
Sand	200
Red Bed	290
Red Bed & Shale	677
Anhydrite	697
Shale & Shells	1370
Shale & Lime	1550
Lime & Shale	2025
Shale & Lime	2435
Shale & Shells	2600
Lime & Shale	3489
Lime & Sand	3508
Arbuckle	3625
RTD	3625

Ran 7 jts. (282') 8 5/8" casing set at 289' with 250 sacks. Cement circulated.

- DST #1 3258-3305
- DST #2 mis-run
- DST #3 mis-run
- DST #4 3305-3329
- DST #5 3360-3387
- DST #6 3508-3513
- DST #7 3511-3518
- DST #8 3514-3523
- DST #9 3521-3528
- DST #10 3528-3535
- DST #11 3544-3560

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 23 1970
 CONSERVATION DIVISION
 Wichita, Kansas

Ran electric log.


Ran 117 jts. (3631') 5 1/2" casing set at 3624' with 100 sacks cement.

AFFIDAVIT

State of Kansas)
) ss:
 County of Barton)

The undersigned, being duly sworn on oath, states that the above statement and log are a true and correct record and log of the well drilled at the location above described.

William S. Schachle
 William S. Schachle, Affiant



Theora Holleman
 Theora Holleman, Notary Public

Subscribed and sworn to before me this 12th day of January, 1970.

Commission expires: April 18, 1972.