


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford County. Sec. 17 Twp. 21 Rge. 12 (E) (W) x

NORTH



Locate well correctly on above Section Plat

Location as "NE/CNW%SW%" or footage from lines NE/4
Lease Owner Hudson Petroleum Inc.
Lease Name Westafer Well No. #1
Office Address Box 333, 4720 Rainbow Kansas City, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed 9-14-63 19____
Application for plugging approved _____ 19____
Plugging commenced 10-1-63 19____
Plugging completed 10-12-63 19____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3505' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded back to 3475' - mixed and dumped 5 sacks cement with dump bailer.
Got Sun Oilwell Cementing to squeeze well. Pumped in 10 sacks jell and 70 sacks cement.
Took swedge off, run 5 sacks cement for top cap.

RECEIVED
STATE CORPORATION COMMISSION

10-15-63 OCT 15 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec.
Box 364, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 14 day of October, 1963

My commission expires 24 October 1964

Sidney D. Miller
Notary Public.

WESTAFER NO. 1 WELL

LOCATION:	NE/4 NW/4 NE/4 Section 17-21-12W Stafford County, Kansas	COMMENCED: 12- 8-59 COMPLETED: 12-17-59
OPERATOR:	Hudson Petroleum Company 1112 Southwest Boulevard Kansas City, Kansas	
CONTRACTOR:	Birmingham-Bartlett Drilling Co. 300 Kaufman Building Wichita 2, Kansas	
SURFACE CASING:	8-5/8" casing cemented at 273' with 225 sacks cement and 4 c.c.	
OIL STRING:	5-1/2" casing set at 3496' with 100 sacks cement	

LOG

(Figures indicate bottom of formation)

0 -	242	Sand
	273	Shale
	672	Shale and red bed
	700	Anhydrite
	790	Red bed and shale
	1650	Shale and shells
	1730	Lime
	2300	Lime and shale
	2510	Broken Lime
	3232	Shale and lime
	3505	Lime
	3505	Rotary total depth

RECEIVED
STATE CORPORATION COMMISSION

NOV 1 1963

CONSERVATION DIVISION
Wichita, Kansas

The undersigned, Richard Hindery, one of the partners of Birmingham-Bartlett Drilling Co., hereby certifies that the above is a true and correct log of the formations encountered in drilling the Westafes No. 1 Well as shown in the daily drilling reports.

BIRMINGHAM-BARTLETT DRILLING CO.

By Richard Hindery
Richard Hindery, Partner

Subscribed and sworn to before me
this 18th day of December 1959.

Beverly Larson
Beverly Larson, Notary Public

My commission expires October 2, 1962.