

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 14 Twp. 21S Rge. (E) 12 (W)

Location as "NE/CNW/SW" or footage from lines SE NW SE

Lease Owner Chief Drilling Co., Inc.

Lease Name Roberts Well No. 1

Office Address P. O. Box 97, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed 4-1-61 19

Application for plugging filed 3-31-61 19

Application for plugging approved 3-31-61 19

Plugging commenced 3-31-61 19

Plugging completed 4-1-61 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot, St. John, Kansas

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3600' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	244'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set wooden plug and 1/3 sack hulls at 215'.  
Mixed 20 sacks cement through drill pipe.

1/3 Sack of Hulls, wooden plug set at 35'.  
Mixed 10 sacks cement through drill pipe.

RECEIVED  
STATE CORPORATION COMMISSION

4-4-61 APR 4 1961

CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Chief Drilling Co., Inc.

Address P. O. Box 97, Great Bend, Kansas

STATE OF KANSAS COUNTY OF BARTON, ss.

V. Richard Hoover, President (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. Richard Hoover  
V. Richard Hoover, President

(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of April, 19 61

My commission expires October 3, 1964

Helen E. Fischer  
Helen E. Fischer

Notary Public.



WELL LOG

Chief Drilling Co., Inc.  
P. O. Box 97  
Great Bend, Kansas

No. 1 Roberts  
SE NW SE Sec. 14-21S-12W  
Stafford County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 3-24-61  
Completed: 4-1-61

Casing Record: 8-5/8" @ 244' cemented with 300 sacks Sunset Cement.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Sand and Shale	0	244'	1835' Gr.
Red Bed	244'	622'	1837' D.F.
Anhydrite	622'	640'	1840' K.B.
Red Bed and Shale	640'	940'	
Shale and Shells	940'	1480'	
Lime and Shale	1480'	2290'	
Shale and Lime	2290'	2580'	
Lime	2580'	2655'	
Lime and Shale	2655'	2970'	
Lime and Shale Streaks	2970'	3045'	
Lime	3045'	3110'	
Lime and Shale	3110'	3210'	
Lime	3210'	3498'	
Conglomerate	3498'	3600'	
Total Depth	3600'		

  

<u>FORMATION TOPS</u>	
Anhydrite	622' (+1218)
Heebner	3070' (-1230)
Brown Lime	3221' (-1381)
Lansing	3234' (-1394)
Base Kansas City	3467' (-1627)
Conglomerate	3498' (-1658)
Total Depth	3600' (-1760)

STATE OF KANSAS, COUNTY OF BARTON) SS.

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the SE NW SE Sec. 14-21S-12W, Stafford County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

*V. Richard Hoover*  
V. Richard Hoover, President

Subscribed and sworn to before me this 1st day of April, 1961.

My commission expires: October 3, 1964.

*Helen E. Fischer*  
Helen E. Fischer, Notary Public

FILED  
STATE CORPORATION COMMISSION

APR 4 1961

CONSERVATION DIVISION  
Topeka, Kansas