


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Stafford County, Sec. 9 Twp. 21 Rge. 12 (E) W (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines. NE NW NE
Lease Owner Duke & Wood Drilling Company
Lease Name Burhenn Well No. 2
Office Address P.O. Box 123, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 7 1954
Application for plugging filed September 7 1954
Application for plugging approved September 7 1954
Plugging commenced September 7 1954
Plugging completed September 7 1954
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3465 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	245	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 240 ft., set bottom plug with 2 gal. hulls in sack and 20 sacks cement. Filled with heavy mud to 35 ft., set top plug. Put 2 gal. hulls under plug and 10 sacks cement on top of plug. Filled to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke & Wood Drilling Company
Address P.O. Box 123, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Lynn O. Duke (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lynn O. Duke
Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of September, 19 54

My commission expires April 29, 1957

24-7988-B 3-53-20M

Notary Public.

PLUGGING
PAR SEC 9 T 21 R 12W
BOOK PAGE 63 LINE 3

CONSERVATION DIVISION
Wichita, Kansas
9-16-54

WELL LOG
 Burhenn #2
 NE NW NE of Sec. 9-21-12W
 Stafford County, Kansas

Started: August 28, 1954
 Completed: September 7, 1954

Elevation 1841 KB
 Anhydrite 619 (-1222)
 Heebner 3054 (-1213)
 Lansing 3200 (-1359)
 Conglomerate 3407 (-1566)
 Arbuckle 3457 (-1616)

0-145	Sand and clay
145-225	Sand and red rock
225-245	Red bed
245-619	Red bed
619-648	Anhydrite
648-1200	Shale and shells
1200-1400	Salt and shale
1400-1660	Shale and shells
1660-1715	Shale, shells, lime streaks
1715-2000	Lime and shale
2000-2115	Lime
2115-2720	Lime and shale
2720-2860	Lime and shale
2860-3120	Lime
3120-3365	Lime
3365-3415	Lime and Conglomerate
3415-3465	Lime
3465	TOTAL ROTARY DEPTH

A F F I D A V I T

STATE OF Kansas, COUNTY OF Barton, SS

I, Lynn O. Duke, of the DUKE & WOOD DRILLING COMPANY
 being first duly sworn on oath, state; That I have knowledge of the facts,
 statements and matters herein contained and that the same are true and
 correct.

Lynn O. Duke
 Partner

Subscribed and sworn to before me this 15th day of September 1954.

Dean E. Cooley
 Notary Public

My commission expires: April 29, 1957.

