

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Stafford County, Sec. 9 Twp. 21S Rge. (E) 12W(W)

Location as "NE/CNW/SW" or footage from lines SW SE NE

Lease Owner Circle Oil Company, Inc.

Lease Name BURHENN Well No. 1

Office Address 500 Bitting Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed October 14, 19 66

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced October 14, 19 66


Plugging completed October 14, 19 66

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Archie Elving)

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 3490 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	267'	8-5/8"	10/8/66	----
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud from Total Depth to 240 Feet; Hull Plug and HOWCO Plug and 25 sacks of cement thru the Drill Pipe; Mud to 40 feet; 1/2 sack Hulls and Plug bridged with Kelley and 11 sacks of cement to Base of Cellar; 2 sacks in Rat Hole. Job completed at 7:45 A.M.

STATE CORPORATION COMMISSION

OCT 19 1966

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sage Drilling Co., Inc.

Address 500 Bitting Building, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Lawrence F. Gray (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lawrence F. Gray

500 Bitting Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 18th day of October 19 66

Louise K. Whitted
Louise K. Whitted - Notary Public.

My commission expires November 26, 1966

DRILLERS LOGBURHENN NO. 1

CASING RECORD:	COMPANY: Circle Oil Co., Inc.	DESCRIPTION:
8-5/8" @ 267' w/230 sax cement	CONTRACTOR: Sage Drilling Co.	SW SE NE Sec. 9-21S-12W Stafford Co., Kansas
TOTAL DEPTH: 3490'	COMMENCED: October 8, 1966	ELEVATION: 1845KB
	COMPLETED: October 14, 1966	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil & Sand	0	30	
Sand	30	225	
Shale	225	267	
Red Bed & Shale	267	632	
Anhydrite	632	653	
Shale	653	1135	
Shale & Shells	1135	1485	
Sandy Lime & Shale	1485	1680	
Shale & Lime	1680	1994	
Lime & Shale	1994	2200	
Shale & Lime	2200	2600	
Lime & Shale	2600	3212	
Lime	3212	3375	
Lime & Shale	3375	3490	

RECEIVED
STATE CORPORATOR COMMISSION
OCT 19 1966
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING COMPANY, INC.

By Lawrence F. Gray
Lawrence F. Gray

Subscribed and sworn to before me this 18th day of October, 1966.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1966.