

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Stafford County, Sec. 9 Twp. 21 Rge. 12 (E) (W)

Location as "NE/CNW%SW%" or footage from lines NE NE SE
Lease Owner Morris Sitrin, Inc.
Lease Name Setser #2 Well No. _____
Office Address ~~Oklahoma~~ Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 11/3/70 _____ 19____
Plugging completed 12/4/70 _____ 19____
Reason for abandonment of well or producing formation depleted.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Russell Biberstein
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3482' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8 | 256 | none |
| | | | | 5 1/2" | 3477' | 2719' |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3480' and ran sand to 3450', ran 5 sacks of cement.
Loaded hole with water, shot pipe at 2810', 2717', worked pipe loose
and pulled 85 joints. Allied pumped 3 sacks hulls, 15 mud and 100
cement to plug well.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
JAN 7 1971
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Noel Knight*
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of December, 19 70

My commission expires 2/15/71

Margaret Malcher
Notary Public.

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 800 EAST MURDOCK - WICHITA, KANSAS

COPY

COMPANY **CIRCLE OIL, INC.** 15,185,30342,0000

SEC. 9 T. 21 R. 12W
 LOC. NE NE SE

FARM **Setser** NO. 2

TOTAL DEPTH **3482**

COUNTY **Stafford**
 KANSAS

COMM. **10-1-66**

COMP. **10-7-66**

SHOT OR TREATED

CONTRACTOR **Sage Drlg.**

ISSUED **1-7-67**

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 13 1970
 CONSERVATION DIVISION
 Wichita, Kansas

| | | | |
|--|--|--|--|
| | | | |
| | | | |
| | | | |
| | | | |

CASING

20 10
 15 8 5/8" @ 256' w/ 255 SX
 12 6
 13 5" @ 3477' w/125 SX

ELEVATION **1847' KB** WCPD 122

PRODUCTION **PMP 84 BOPD,**
 TR Wtr., GR 38 (Arb 3477-82)

FIGURES INDICATE BOTTOM OF FORMATIONS

| FORMATION | FROM | TO | REMARKS |
|------------------------|------|------|-----------------|
| Surface Soil | 0 | 256 | TOPS: SAMPLE |
| Red Bed & Shale | 256 | 637 | |
| Anhydrite | 637 | 659 | Heebner 3072 |
| Shale & Shells | 659 | 1300 | Toronto 3093 |
| Shale | 1300 | 1710 | Douglas 3108 |
| Shale & Shells & Limes | 1710 | 2025 | Brown Lime 3205 |
| Lime & Shale | 2025 | 2405 | Lansing 3220 |
| Shale & Lime | 2405 | 2708 | B/Kansas C 3431 |
| Lime & Shale | 2708 | 3264 | Simpson 3439 |
| Lime | 3264 | 3290 | Arbuckle 3476 |
| Lime & Shale | 3290 | 3409 | |
| Lime | 3409 | 3435 | |
| Lime & Shale | 3435 | 3482 | |

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Lawrence F. Gray
 Lawrence F. Gray

Subscribed and sworn to before me this 12th day of October, 1966.

Louise K. Whitted
 Louise K. Whitted, Notary Public

My commission expires:
 November 26, 1966.