


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
900 Bittling Building
Wichita, Kansas

Stafford County. Sec. 9 Twp. 21 Rge. 12 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NW NE NW
Lease Owner Duke & Wood Drilling Company
Lease Name Krueger Well No. 2
Office Address Box 194, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed July 2, 19 52
Application for plugging filed July 2, 19 52
Application for plugging approved July 2, 19 52
Plugging commenced July 2, 19 52
Plugging completed July 2, 19 52
Reason for abandonment of well or producing formation dry



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3478 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	223'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 210ft., dumped 1/2 sack hulls, set plug, dumped 20 sacks of cement, wet through drill pipe. Filled with heavy mud to 35 ft., 1/2 sack hulls, top plug hung on wire, dumped 10 sacks of cement, filled to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Duke & Wood Drilling Company
Address Box 194, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Cecil M. Olson (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Cecil M Olson
Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of July 19 52

My commission expires April 29, 1953.

Dean L. Cooley
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

JUL 30 1952 7-30-52

PLUGGING
FILE SEC 9 T 21 R 12
BOOK PAGE 28 LINE 29

CONSERVATION DIVISION
Wichita, Kansas

WELL LOG
Krueger #2
NW NE NW of Section 9-21-12W
Stafford County, Kansas

Started: June 19, 1952
Completed: July 2, 1952

Elevation 1844 KB
Anhydrite 612 (-1232)
Heebner 3057 (-1215)
Lansing 3205 (-1361)
Arbuckle 3475 (-1631)

0-90	Sand
90-190	Sand, clay and shale
190-220	Red rock
220-480	Red bed and shale
480- 612	Red bed
612-644	Anhydrite
644-1110	Shale and shells
1110-1340	Salt and shale
1340-1545	Shale, shells and lime
1545-2017	Lime and shale
2017-2470	Lime and shale
2470-2820	Lime and shale
2820-2965	Lime
2965-3125	Lime
3125-3195	Lime and shale
3195-3315	Lime
3315-3360	Lime
3360-3435	Lime
3435-3475	Conglomerate
3475-3478	Arbuckle
3478	ROTARY TOTAL DEPTH

A F F I D A V I T

STATE OF Kansas, COUNTY OF Barton, SS

I, Lynn O. Duke, of the DUKE & WOOD DRILLING COMPANY being first duly sworn on oath, state; That I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.

Lynn O. Duke
Partner

Subscribed and sworn to before me this 19th day of July 1952.

Dean C. Cooley
Notary Public

My commission expires: April 29, 1953

RECEIVED
CORPORATION COMMISSION
PLUGGING
FILE SEC 9-21-12W JUL 30 1952
BOOK PAGE 28 LINE 307 CONSERVATION DIVISION
Wichita, Kansas