


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford County. Sec. 9 Twp. 21 Rge. 12 (W) W (W)
Location as "NE/CNW%SW%" or footage from lines NE NE NW
Lease Owner Frank G. Wood Drilling Company
Lease Name Krueger Well No. 1
Office Address Box 619, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed March 1951
Application for plugging filed August 16 1956
Application for plugging approved August 17 1956
Plugging commenced August 25 1956
Plugging completed August 27 1956
Reason for abandonment of well or producing formation Depleted

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production July 30 1956
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundege
Producing formation Arbuckle Depth to top Bottom Total Depth of Well 3490 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	236'	None
				5 1/2"	3490'	2630'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug back with sand to 3463 ft., dumped 5 sacks cement. Filled hole with mud to 230 ft., set 5 ft. rock bridge, dumped 20 sacks cement on plug. Filled hole with mud to 35 ft., set 5 ft. rock bridge, dumped 10 sacks of cement on plug, filled to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ace Pipe Pulling Co.
Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Loren J. Siefkes (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Loren J. Siefkes
Hoisington, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 31 day of August, 19 56
Dean E. Hooley Notary Public.

My commission expires April 29, 1957.

STATE CORPORATION COMMISSION

SEP 3 1956 9-3-56

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 9 T. 21 R. 12W
BOOK PAGE 90 LINE 40

15.185.12836.0000

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **DUKE & WOOD**

SEC. 9 T. 21 R. 12W

FARM **Krueger**

NO. 1

LOC. NE NE NW

TOTAL DEPTH **3490**

COUNTY **Stafford**


COMM. **3-9-51**

COMP. **3-20-51**

SHOT OR TREATED

CONTRACTOR

ISSUED **5-12-51**



CASING

No casing record.

ELEVATION **1844 R.B.**

PRODUCTION **I.P.P. 174 BO & NW**

FIGURES INDICATE BOTTOM OF FORMATIONS

sand, clay & redbed	236
red bed, shale & sand	621
anhydrite -	660
shale & anhydrite	
shells	770
shale, shells & salt	1245
shale, shells & lime	1630
shale & lime	2750
lime	3421
conglomerate	3458
arbuckle	3490
Total Depth	

Tops:	
Anhydrite	621
Heebner	3055
Lansing	3199
Conglomerate	3421
Arbuckle	3458

RECEIVED
STATE COMMISSION
AUG 12 1955
DIVISION

PLUGGING
FILE SEC 9 T. 21 R. 12W
BOOK PAGE 90 LINE 40