


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section Plot

Stafford County, Sec. 9 Twp. 21 Rge. 12 ~~XX~~/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SW/NE/SE
Lease Owner The Tipton Corporation
Lease Name Setser Well No. #1
Office Address P. O. Box 157 - Hays, Ks. 67601
Character of Well (Completed as Oil, Gas or Dry Hole)
Oil
Date Well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced June 11, 1981 19
Plugging completed June 25, 1981 19
Reason for abandonment of well or producing formation
Depleted
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie
Producing formation Depth to top Bottom Total Depth of Well 3489
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	274'	NONE
				4 1/2"	3484'	2728.70'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
 feet for each plug set.

Dumped sand to 3200' and five (5) sacks cement.
Shot pipe @ 2750'.
Pulled 67 joints of 4 1/2" casing.
Squeezed well with fifteen (15) sacks gel, eight (8) sacks hulls,
ten (10) sacks gel, one hundred twenty-five (125) sacks 50/50 pozmix
cement with 4% added gel and 3% CC.

7-2-81

RECEIVED
STATE CORPORATION COMMISSION

JUL - 2 1981

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF KANSAS COUNTY OF BARTON
James W. Rockhold (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature)

James W. Rockhold

James W. Rockhold - Box 698 - Great Bend, Ks.

(Address) 67530

SUBSCRIBED AND SWORN TO before me this 30th day of June, 1981

Ruth Brack

Notary Public.

My commission expires



15.185.21175.0000

ROGO DRILLING, INC.

GREAT BEND, KANSAS 67530

P. O. BOX 11
1819 ELEVENTH STREET
TELEPHONE (316) 792-1383

DRILLERS WELL LOG

Setser #1
SW NE SE, Section 9-21S-12W
Stafford County, Kansas

Operator: The Tipton Corporation
Box 157
Hays, Kansas 67601

Date Commenced: February 19, 1981
Date Completed: February 24, 1981

Elevation: 1850' K.B.
Total Depth: 3489'

Casing: 8 5/8" @ 274' w/200 Sk.
4 1/2" 3484' w/150 Sk.

DEPTH		FORMATION	SAMPLE TOPS	
FROM	TO			
0	640	Surface Soil, Sand & Shells	Anhydrite	640
640	663	ANHYDRITE	Heebner	3065
663	1900	Shale, Shells & Lime	Toronto	3082
1900	3065	Lime & Shale	Douglas	3098
3065	3070	HEEBNER Shale	Brown Lime	3207
3070	3097	Shale, Silt & Lime	Lansing	3222
3097	3435	Lime & Shale	Base Kansas City	3435
3435	3459	Shale & Chert	Conglomerate	3440
3459	3481	Shale & Sand	Simpson	3459
3481	3489	Dolomite	Arbuckle	3481
	3489	Rotary Total Depth	Rotary Total Depth	3489

I, Richard L. Miller, certify this is a correct copy of the Driller's Log from the well drilled at the above location, to the best of my knowledge and belief.

Signed Richard L. Miller
Richard L. Miller

181

RECEIVED
STATE CORPORATION COMMISSION

JUN - 5 1981

CONSERVATION DIVISION
Wichita, Kansas