


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Stafford County. Sec. 5 Twp. 21 Rge. 12 (W)  
Location as "NE/CNW/SW" or footage from lines NE SW NW  
Lease Owner Sterling Drilling Company  
Lease Name Sieker Well No. 2  
Office Address Box 127, Sterling, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 2-25-1961  
Application for plugging filed 2-25-1961  
Application for plugging approved 2-25 19 61  
Plugging commenced 2-25 19 61  
Plugging completed 2-25 19 61  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production --- 19---  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3545 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	288'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy mud to 275'. Howco plug @ 275' with 1/2 sack hulls, 20sacks cement thru drill pipe. Heavy mud to 35'. Plug at 35' with 1/2 sack hulls, 10 sacks cement thru drill pipe to base of cellar. Plugging completed 4:00 A.M. 2-25-61.

RECEIVED  
STATE CORPORATION COMMISSION

FEB 28 1961

CONSERVATION DIVISION  
Wichita, Kansas

2-28-61

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company  
Address Box 127, Sterling, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.  
F. A. Wuellner, Secretary (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. STERLING DRILLING COMPANY

(Signature) F. A. Wuellner  
F. A. Wuellner  
Sterling, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of February, 19 61

Bernard Zaudermilch  
Notary Public.

My commission expires My Commission Expires Jan. 22, 1962



STERLING DRILLING COMPANY  
Sterling, Kansas

WELL LOG - - - - - Sieker #2  
Located: NE SW NW, Section 5-21-12, Stafford County, Kansas

OWNER: Sterling Drilling Company, et al  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: 2-17-61  
COMPLETED: 2-25-61

ROTARY TOTAL DEPTH: 3545'

LOG

0	-	200	Clay & Sand
200	-	290	Red Bed
290	-	970	Shale & Red Bed
970	-	1325	Shale
1325	-	2035	Shale & Lime
2035	-	2265	Lime
2265	-	2860	Shale & Lime
2860	-	3030	Lime
3030	-	3210	Lime & Shale
3210	-	3445	Lime
3445	-	3494	Conglomerate
3494	-	3505	Lime
3505	-	3545	Arbuckle T.D.

CASING RECORD

Set 8-5/8" Surface Casing @  
288' K.B. with 275 sacks Cement.

Plugged and Abandoned

**RECEIVED**  
STATE CORPORATION COMMISSION

FEB 28 1961

CONSERVATION DIVISION  
Wichita, Kansas