

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Stafford County, Sec. 5 Twp. 21S Rge. 12 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE NE NW  
Lease Owner Beardmore Drilling Company  
Lease Name Sieker Well No. 1  
Office Address 603 Petroleum Building, Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed April 23 19 53  
Application for plugging filed April 23 19 53  
Application for plugging approved April 23 19 53  
Plugging commenced April 23 19 53  
Plugging completed April 23 19 53  
Reason for abandonment of well or producing formation dry hole

NORTH


Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes  
C. D. Stough

Name of Conservation Agent who supervised plugging of this well  
Producing formation Depth to top Bottom Total Depth of Well 3510 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Sand		0	220			
Shale - Shells		220	252	8-5/8"	252	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from top feet to bottom feet for each plug set.

Heavy mud from 240' to 3510'

Wood Plug @ 240'

20 Sacks Cement from 180' to 240'

Heavy Mud from 25' to 180'

Wood Plug @ 25'

10 Sacks Cement from surface to 25'

RECEIVED  
STATE CORPORATION COMMISSION

MAY - 1 1953

5-1-53

CONSERVATION DIVISION

Name of Plugging Contractor Beardmore Drilling Company Wichita, Kansas  
Address 603 Petroleum Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
I, Heber Beardmore (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Heber Beardmore*  
603 Petroleum Building, Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of April, 19 53  
*Leonard P. Tolk*

My commission expires January 28, 1956 Notary Public.

PLUGGING  
FILE SEC 5 T 21 R 12 W  
BOOK PAGE 96 LINE 21

SIEKER NO. 1

SE NE NW  
 Section 5-21S-12W,  
 Stafford County, Kansas

Drilled for: Beardmore, O. A. Sutton,  
 & Oil Trading Assoc., Inc.  
 Drilled by: Beardmore Drilling Company

## Casing Record:

8-5/8" 252<sup>f</sup> w/135 Sacks.

Drilling Commenced: April 12, 1953  
 Drilling Completed: April 23, 1953

Elevation: DF 1851  
 GR 1849

<u>FORMATION</u>	<u>DEPTH</u>
Sand	220
Shale - Shells	252
Red Rock - Shale - Shells	655
Anhydrite	675
Shale - Shells	1470
Shale - Lime	1610
Lime Broken	1820
Lime	1955
Lime - Shale	2160
Shale - Shells	2300
Shale - Lime	2740
Lime - Shale	3020
Lime	3075
Lime - Shale	3195
Lime	3510

D & A

TOPS:

Heebner	3065
Brown Lime	3192
Lansing	3210
Arbuckle	3448

DST #1 - 3214-3263 - Open 1 hour, Shut in 15 Minutes. Recovered 15<sup>f</sup> Mud.  
 BHP Zero #. Weak blow throughout the hour.

DST #2 - 3449-3470 - Open 1 hour, shut in 15 minutes. Recovered 60<sup>f</sup> oil  
 cut mud. Bhp 450#.

DST #3 - 3470-3490 - Open 1 hour, 20 minutes, shut in 15 minutes. Recovered  
 60<sup>f</sup> muddy water. BHP 650#.

STATE OF KANSAS


ss

COUNTY OF SEDGWICK

I, the undersigned, being duly sworn on oath state that the above and within statement is a true and correct record and log of the well drilled on the location above-described, to the best of my knowledge and belief.



Subscribed and sworn to before me this 24th day of April, 1953.

  
 Notary Public

My Commission Expires: January 28, 1956

RECEIVED  
 STATE CORP. REG. DIVISION

MAY - 1 1953

PLUGGING  
 FILE SEC. 5 T 21 R 12 W  
 BOOK PAGE 96 LINE 21

CONSERVATION DIVISION  
 Wichita, Kansas