


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 13 Twp. 21 Rge. 12 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE SE NW
Lease Owner The Shallow Water Refining Company
Lease Name Tindall "A" Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 10-28-66 _____ 19____
Plugging completed 11-3-66 _____ 19____
Reason for abandonment of well or producing formation Depleted.



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3546 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	242'	None
				5-1/2"	3542'	1680'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to plug-back @ 3492', sanded hole to 3400' and dumped 5 sacks of cement @ 3400' with dump bailer. Pulled 5 1/2" casing to 400' and pumped in 12 sacks of gel mud. Pulled 5 1/2" casing to 250' and pumped in 25 sacks of cement. Pulled balance of 5 1/2" casing, checked fluid to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

NOV 14 1966

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of November, 19 66

My commission expires May 20, 1968
Milton J. Volin Notary Public.

15.185.00206.0000

COPY


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
608 East Murdock, Wichita, Kansas

Company- ISERN DRILLING CO, ET AL
Farm- Eveleigh No. 1

SEC. 13 T. 21 R. 12W
NE SE NW

Total Depth. 3540
Comm. 10-30-53 Comp. 11-9-53
Shot or Treated.
Contractor.
Issued. 12-5-53

County Stafford
KANSAS



8 5/8" CASING:
242'

Elevation. 1823 DE

Production. dry

Figures indicate Bottom of Formations.

sand	130
sand & shale	222
redrock	575
Anhydrite	605
shale & shells	1130
salt	1310
shale & shells	1400
shale & lime	1795
sand	1810
lime & shale	2205
shale & shells	2770
lime & shale	3250
lime	3445
Conglomerate	3492
Arbuckle	3540
Rotary Total depth	

Tops: RBM	
Heebner	3042
Brown Lime	3169
Lansing	3188
Conglomerate	3425
Simpson	3447
Arbuckle	3489

RECEIVED
STATE CORPORATION COMMISSION

JUL 22 1966

CONSERVATION DIVISION
Wichita, Kansas