


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Stafford County, Sec. 13 Twp. 21 Rge. (X) 12 (W)

NORTH



Locate well correctly on above  
Section Plat

Location as "NE/CNW/SW" or footage from lines NE SE NW  
Lease Owner Isern Drilling Company  
Lease Name Eveleigh Well No. 1  
Office Address Box 45, Ellinwood, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed November 9, 1953 19  
Application for plugging filed November 9, 1953 19  
Application for plugging approved November 9, 1953 19  
Plugging commenced November 9, 1953 19  
Plugging completed November 9, 1953 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3540 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface Pipe	0	242'	8-5/8"	242'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud to 240'. Bridged hole at 240'. Run 20 sacks cement 240' up. Bridge hole at 40'. Run 10 sacks cement, plug 40' to base of cellar.

11-13-53

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Isern Drilling Company  
Address Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
T. M. M. Shropshire (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. M. M. Shropshire  
Lyons, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 10th day of November, 19 53

George A. Meyer  
Notary Public.

My commission expires Feb. 10, 1955.

24-7868-S 3-53-20M  
PLUGGING  
FILE SEC 13 T 21 R 12W  
BOOK PAGE 14 LINE 43

## WELL LOG

ISERN DRILLING COMPANY ETAL, Owner - Eveleigh #1  
NE/4 SE/4 NW/4 Section 13, Township 21, Range 12W,  
Stafford County, Kansas

Elevation: 1823 DF

Figures indicate bottom of formation  
0 to 130 sand

## PIPE RECORD:


8-5/8" set at 242'

TOPS: RBM

Heebner	3042
Brown Lime	3169
Lansing	3188
Conglomerate	3425
Simpson	3447
Arbuckle	3489

222	sand & shale
575	Red Rock
605	Anhydrite
1130	shale & shells
1310	salt
1400	shale & shells
1795	shale & lime
1810	sand
2205	lime & shale
2770	shale & shells
3250	lime & shale
3445	lime
3492	Conglomerate
3540	Arbuckle
3540	Total Rotary Depth
	D&A

Rotary Commenced 10-30-53  
Completed 11-9-53



STATE OF KANSAS )  
COUNTY OF BARTON ) SS

I, Warren O. Johnson, Geologist on the above-described well, being first duly sworn on oath, declare: That I have knowledge of the facts, statements and matters herein contained pertaining to the log of the above-described well, as filed, and that the same are true and correct.

RECEIVED  
CORPORATION COMMISSION

NOV 13 1953

CONSERVATION DIVISION  
Wichita, Kansas

Subscribed and Sworn to before me this 12th day of November, 1953.

*Warren O. Johnson*

*George A. Meyer*  
Notary Public

My commission expires Feb. 10, 1955.