

WELL PLUGGING RECORD

FORMATION PLUGGING RECORD

STATE OF KANSAS STATE CORPORATION COMMISSION

Give All Information Completely Make Required Affidavit Mail or Deliver Report to: Conservation Division State Corporation Commission 800 Bittling Building Wichita, Kansas

Strike out upper line when reporting plugging off formations.

NORTH

Section Plat grid with 4 columns and 4 rows.

Locate well correctly on above Section Plat

Stafford County, Sec. 14 Twp. 21 Rge. (E) 12 (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. NE 1/4 NE NE

Lease Owner Adair & Morton

Lease Name Roberts Well No. #1

Office Address Wichita, Kansas.

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed Mar. 2 19.42

Application for plugging filed Mar. 2 19.42

Application for plugging approved Mar. 2 19.42

Plugging commenced Mar. 2 19.42

Plugging completed Mar. 5 19.42

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19.

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. F. Alexander

Producing formation None Depth to top Bottom Total Depth of Well 3667 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Contains two entries for casing sizes 5 1/2" and 8 5/8".

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Well was cemented from 3667' to 3380' - filled with mud to 3300' - put 10 sacks of cement at 3300'. Filled with mud from 3300' to 297' put bridge in hole at 297' and cemented with 10 sacks. Mudded well to 30' put 10 sacks of cement to top of surface.

Handwritten notes: 14 21 12W, 27 10

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Adair & Morton

Address Wichita, Kansas.

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Handwritten signature of D. H. Gunn

SUBSCRIBED AND SWORN to before me this 11th day of March

Notary Public stamp: MAR 1 1945, 3-16-42, Clyted Smalley

My commission expires Dec. 6, 1945



COMPANY: Adair & Norton LOCATION: C NE 1/4 NE 1/4  
 CONTRACTOR: Hannum Drilling Co., Inc. Section 16-21-12W  
 FARM: Roberts, Well No. 1 Stafford County, Kans.

ELEVATION: 1842'  
 PRODUCTION: D. & A.

CASING RECORD

COMMENCED: Jan. 20, 1942 8 5/8" 294' 135 Sacks Cement  
 COMPLETED: March 6, 1942. 5 1/2" 3663 125 " "

FORMATION	DEPTH	FORMATION	DEPTH
Surface & Sand	40'	Brown Lime	3215'
Sand	68	Shale	3226
Shale & Shells	100	Gray Lime	3300
Sand	200	Line	3390
Red Rock & Shells	575	Line	3465
Red Rock	750	Shale & Shells	3491
Shale & Shells	760	Cherty Conglomerate	3505
Anhydrite	790	Maroon & Green slickensided	
Red Rock	895	Shale	3515
Shale & Shells	1195	Shale	3553
Shale, Salt & Shells	1455	Arbuckle Dolomite	3555
Shale & Salt	1458	Arbuckle Dolomite	
Anhydrite	1590	Coring	3565-3563
Lime, Brk.	1654	Full Recovery	
Sandy Lime	1805	Line	3667
Sandy Lime & Shale	1930	Total Depth.	
Brk. Sandy Lime	2185		
Brk. Lime & Shale	2325	Drilled with Cable tools 3563- 3667	
Shale & Shells	2495	Plugging Record Attached.	
Brk. Sandy Lime	2643		
Brk. Lime	2598		
Shale & Shells	2694	Kansas City Lime perforated between	
Brk. Lime	2785	3305'-3311' with 20 shots - no oil	
Line	2900	or water.	
Brk. Lime	3095		
Line	3075	Kansas City Lime Perforated between	
Brk. Lime	3211	3354' - 3360' with 20 shots - no	
		oil or water.	

I hereby certify this to be a correct and accurate log of the above described well as shown by the drilling reports.

*E. L. Hannum*

Subscribed and sworn to before me this 11th day of March, 1942.

*Clyde S. Smalley*  
 Notary Public

My Commission Expires Dec. 8, 1945.

FILE 14 21-12W  
 BOOK PAGE 27 LINE 12

