


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Stafford County, Sec. 14 Twp. 21 Rge. 12 (E) W (W)
C NW SW

NORTH



Locate well correctly on above Section Plat

Location as "NE/CNW/SW" or footage from lines _____
Lease Owner Walter J. Nelson
Lease Name Roberts B#1 Well No. _____
Office Address Salina, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 1/27/68 _____ 19____
Plugging completed 2/9/68 _____ 19____
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3831 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	268'	none
				5-1/2"	3830'	2596'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole, bridge in hole at 672',
Checked hole to 3831', pushed plug to 3300' and ran sand to 3275'.
Ran 5 sacks of cement, worked pipe to 20 1/2" tension. Shot pipe at 2994', worked pipe to 25" tension. Shot pipe at 2900', worked pipe, shot at 2803', 2709', 2584', pulled 81 joints. Set 10' rock bridge at 260' and ran 4 sacks of cement. Bailed hole, ran 21 sacks of cement, mudded hole to 40' and set 10' rock bridge. Ran 10 sacks of cement on top. Tallied pipe.

RECEIVED
STATE CORPORATION COMMISSION
FEB 27 1968
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of February, 19 68

My commission expires: February 15, 1971

Margaret Melcher
Notary Public.

ROTARY DRILLING LOG

OWNER: Walter J. Nelson
 CONT: Walter J. Nelson
 LEASE: Roberts B #1
 LOC: C-NW SW
 14-215-12W

CASING: 268' 8 5/8" Surface casing
 3830' 5 1/2" casing

0 -	40	surface
40 -	78	sand
78 -	116	sandy shale
116 -	159	coarse sand and gravel
159 -	248	sandy shale
248 -	622	shale and shells
622 -	745	anhydrite and shale
745 -	1515	shale and shells
1515 -	1525	lime
1525 -	1735	shale and shells
1735 -	1786	lime
1786 -	2600	shale and shells
2600 -	2735	lime
2735 -	2880	shale and shells
2880 -	3114	lime
3114 -	3133	Heebner shale
3133 -	3148	Toronto lime
3148 -	3257	Douglas shale
3257 -	3273	Iatan lime
3273 -	3501	Lansing K. C. lime
3501 -	3533	Conglomerate
3533 -	3805	Brown and various colored shale and various colored chert
3805 -	3831	Lime and chert

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 25 1968
 CONSERVATION DIVISION
 Wichita, Kansas