

Form CP-3  
Rev. 6-26-62

**KANSAS**  
**STATE CORPORATION COMMISSION**  
**CONSERVATION DIVISION AGENT'S REPORT**

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 31 1966  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Circle Oil Company, Inc.

Complete Address: 500 Bitting Bldg., Wichita, Kansas

Lease Name Christiansen Well No. # 1

Location SE NE NW Sec. 10 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3555'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A  X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Sage Drilling Company, Inc.

Address: 500 Bitting Bldg., Wichita, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 1:45PM Day 28th Month Oct. Year 1966

The Above well was plugged as follows:

275' of 10 3/4" surface pipe, cement circulated with 250 sacks. Fluid  
level in the hole was at 140'. 1st cementing plug and 1/2 sack of hulls  
was pushed in fluid to 260', and cemented with 30 sacks of cement at 260',  
through the drill pipe. Hole was filled with drilling mud to 40'. 2nd  
cementing plug, bridged with 2 sacks of dry cement and 1/2 sack of hulls on  
fluid at 40', and cemented with 13 sacks to the base of the cellar.  
Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: Archie Elving  
Well Plugging Supervisor

DATE 10/31/66  
INV. NO. 4194-W