


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

15-009-15790-00-00  
WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Barton County. Sec. 16 Twp. 16 Rge. 12 (E) (W)  
Location as "NE/CNW/SW" or footage from lines NE/c NE  
Lease Owner Morgenstern & Specter  
Lease Name Jarus Well No. 1  
Office Address Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed 10-22-49 19\_\_  
Application for plugging filed April 2, 1961 19\_\_  
Application for plugging approved April 3, 1961 19\_\_  
Plugging commenced 4/18/61 19\_\_  
Plugging completed 4/21/61 19\_\_  
Reason for abandonment of well or producing formation failure to produce profitably  
If a producing well is abandoned, date of last production 19\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan, Russell, Ks  
Producing formation Arbuckle Depth to top 3327 Bottom 3333 Total Depth of Well 3333 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"OD	175 ft.	none
				5 1/2"OD	3327ft.	2456 feet

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back with sand to 3300 feet. Dumped 5 sacks Cement. Mudded hole to 280 feet. Set a Rock Bridge. Dumped 25 sacks Cement, Mudded hole to 30 feet. Set a Rock-Bridge, Dumped ten sacks Cement.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 9 1961  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor LYNCH CASING PULLING COMPANY NO. 457  
Address R. Rt. 4 GREAT BEND, KANSAS

STATE OF Kansas, COUNTY OF Russell, ss.  
Morgenstern & Specter, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 24th day of April, 1961

My commission expires Dec 1, 1964 [Signature] Notary Public.



15-009-15790-00-00

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
Wichita, Kansas

COPY

Company D. R. LAUCK OIL COMPANY, INC., et al  
Farm Jarvis No. 1

SEC. 16 T. 16 R. 12W  
NE/4 NE

Total Depth. 3333

Comm. 10-5-49

Comp. 10-22-49


County. Barton

KANSAS

Shot or Treated.

Contractor.

Issued. 11-26-49



CASING:

10" set @ 280' w/175 sx.

5" set @ 3327' w/145 sx.

Elevation. \_\_\_\_\_

Production. Est. 100 Bbls.

Figures Indicate Bottom of Formations.

Shale & shells	40
Shale	170
Sand	190
Shale & shells	325
Sand	360
Shale & shells	795
Anhydrite	830
Red rock	1050
Shale & shells	1550
Lime & shale	1665
Broken lime	1760
Lime & shale	1810
Lime	1830
Lime & shale	1910
Lime	2040
Shale & lime	2735
Lime	3329
Arbuckle	3332

Rotary T. D. 3330 DF

Cable Tools:

Lime 3333

Total Depth

FORMATION TOPS:

Hoebner	2964
Br. lime	3053
Wh. lime	3069
Congl.	None
Arbuckle	3327

DST 2908-30 Op. 15 mins. rec. 30' mud

DST 3069-3103, op. 10 mins., good blow, rec. 90' oil & gas cut mud

DST 3146-56, op. 1 hr. rec. 55' water & mud.

800' oil/20 mins @ 3331

2000' oil/2 hrs. @ 3333

500' O.B. 1st hr. 40 bbls; 2d hr. 26 bbls; 3d hr. 24 bbls.