


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

15-009-15798-00-00

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barton County, Sec. 16 Twp. 16 Rge. 12 (E) W (W)

Location as "NE/CNWxSWx" or footage from lines SE NW SE
Lease Owner Franco Western Oil Company
Lease Name Meyerers Well No. 3
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 9-26-61 _____ 19____
Plugging completed 10-3-61 _____ 19____
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Don Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3346 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10"	210'	None
				7"	3333'	1797'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3346', sanded to 3332' and dumped 5 sacks of cement @ 3332' with dump bailer. Pulled 7" casing. Bailed hole to 220', set rock bridge and ran 30 sacks of cement. Mudded hole to 30', set rock bridge and ran 10 sacks of cement to base of cellar.

RECORDED
FILED
STATE CORPORATION COMMISSION
OCT 20 1961

CONSERVATION DIVISION
Wichita, Kansas
10-20-61

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Company
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.
Noel J. Knight (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of October, 1961

My commission expires May 20, 1964 Melton J. Volin Notary Public.

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg., Wichita, Kansas.

15-009-15798-00,00


COPY

POLK • FORTSON • SHELL PETRO.
P. Meyers No. 3.

SEC. 16 T. 16 R. 12W
SE NW SE
990' fr NL 990' fr WL SE $\frac{1}{4}$

Total Depth. 3349' P.B. 3346'
Conn. 9-24-37 Comp. 10-24-37
Shot or Treated.
Contractor. Halmerich & Payne.
Issued. 11-13-37

County. Barton



CASING:
10 $\frac{3}{4}$ " 210'
7" 3333'

Elevation.

Production. Pot. 603 B.
No wtr.

Figures Indicate Bottom of Formations.

surface sand & clay	175
shale & shells	210
red bed	270
anhydrite	275
shale & shells	890
shale red	1125
shale & shells	1240
salt	1275
salt with shale brks	1375
edy lime & shale	1455
edy lime	1460
shale blue	1500
brkn shale & shells	1565
shale & shells	1690
sticky shale	1713
shale	1800
shale & shells	1890
shale	1920
shale & lime	1990
lime	2040
shale	2160
lime	2185
shale	2205
lime	2245
shale	2305
lime	2325
shale	2385
edy lime	2410
shale	2515
lime	2540
shale	2575
brkn lime & shale	2635
shale	2675
lime	2750
shale	2765
lime	2900
lime & chert	2955
lime	2985
shale	3051
lime	3334

Core #1 3334-38 Rec 4'
 $\frac{1}{2}$ ' lime grey with strks
sand
 $3\frac{1}{2}$ ' sand
Core #2 3338-43 Rec 5'
sand cherty
500' oil in $1\frac{1}{2}$ hrs 3338
sand 3349
Total Depth.

Plugged back 3346

RECEIVED
STATE CORPORATION COMMISSION

SEP 8 1961

CONSERVATION DIVISION
Wichita Kansas