


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barton County. Sec. 16 Twp. 16 Rge. 12W E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines S/2 SW/4
Lease Owner Emphasis Oil Operations
Lease Name Marmie #1 Well No. _____
Office Address Russell, Kansas 67665
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plot

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 6/4/80 _____ 19____
Plugging completed 6/10/80 _____ 19____
Reason for abandonment of well or producing formation
depleted

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Rankin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3395
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	250	none
				4 1/2"	3394	2746'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded to 3050' and ran 4 sacks cement. Shot pipe at 2920', 2820', 2728', pulled 72 joints. Pumped 5 sacks hulls, 25 sacks gel and 100 sacks 50-50 posm 4%.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso

CHASE, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of June, 19 80

Margaret Melcher
Notary Public.

My commission expires



RECEIVED
STATE CORPORATION COMMISSION

JUN 12 1980

CONSERVATION DIVISION
Wichita, Kansas

15-009-21896-00-00

EMPHASIS OIL OPERATIONS

P. O. Box 506

Russell, Kansas 67665

DRILLERS LOG

OPERATOR: N-B Company, Inc.
Box 506
b Russell, Kansas 67665

CONTRACTOR: Emphasis Oil Operations
Box 506
Russell, Kansas 67665

LEASE: Marmie WELL: #1

Location: S/2 SW/4
Section 16-16-12W
Barton County, Kansas

Total Depth: 3395'

Elevation:

Commenced: 4-1-80

Completed: 4-9-80

Casing: 8-5/8" @ 250'
4-1/2" @ 3394'

Status: Oil Well

DEPTHS & FORMATIONS.

(All measurements from K.B.)

Soil & Shale	80	Shale & Lime	2170
Shale With Pyrite	257	Lime & Shale	2330
Shale & Red Bed	824	Shale & Lime	2677
Anhydrite	850	Lime & Shale	3360
Shale & Shells	1526	Shale & Sand	3370
Shale	1670	Shale & Quartz (R.T.D.)	3395

STATE OF KANSAS)
) ss
COUNTY OF RUSSELL)

I, Joe K. Branum, of Emphasis Oil Operations, state that the above and foregoing is a true and correct log of the above captioned well.

Joe K. Branum

Subscribed and sworn to before me this 11th day of April, 1980.
My Commission Expires:

Notary Public

RECEIVED
STATE COMMISSION
MAY 19 1980
JOHN W. JONES DIVISION
Topeka, Kansas