

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Barton SEC. 16 TWP. 16 RGE. 12 E/W
Location as in quarters or footage from lines:
C SW SW

Locate Well
correctly on above
Section Platt.

Lease Owner Reif Oil Operations, Inc.
Lease Name Krier Well No. 1
Office Address Box 298 Hoisington, KS 67544
Character of Well (Completed as Oil, Gas or Dry Hole):
Date Well Completed 11-11-82
Application for plugging filed 3-3-83
Plugging commenced 3-3-83
Plugging completed 3-3-83

Reason for abandonment of well or producing formation
not enough oil to be economical

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck

Producing formation _____ Depth to top _____ bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
<u>Lansing</u>	<u>oil & water</u>	<u>3096</u>	<u>3357</u>	<u>4 1/2</u>	<u>3401</u>	<u>2050</u>
<u>Conglomerate Sand</u>	<u>" "</u>	<u>3357</u>	<u>3401</u>	<u>4 1/2</u>	<u>3401</u>	<u>2050</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. 5 sacks cement bottom of 4 1/2" casing, sand to 2566, 5 sacks cement. Fillup to 2260. Pumped 4 sacks hulls, 12 sacks gel, 65 sacks cement, 3 sacks gel, 1 sack hulls, released plug & followed with 100 sacks cement 800# plug down at 11:00A.M.

RECEIVED
STATE CORPORATION COMMISSION
3-17-83
MAR 17 1983

CONSERVATION DIVISION
Wichita Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor D. S. & W. Well Servicing, Inc. unit #1002
operator #6901

STATE OF Kansas COUNTY OF Barton, ss.

Donald J. Reif (~~employee~~) or (~~owner~~) or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God Donald J. Reif

(Signature) Donald J. Reif
Box 298 Hoisington, KS
(Address)

SUBSCRIBED AND SWORN TO before me this _____ day of _____, 19 _____

Notary Public.

My Commission expires: _____

D. S. & W. WELL SERVICING, INC.

P. O. Box 231

02-24-83

19

CLAFIN, KANSAS 67525

No 39880

Company Reif Oil Operations, Inc. Called by _____

Address P. O. Box 298, Hoisington, Kansas 67544 E.O. or F.O. No. _____

Lease Krier Well No. 1

WELL PULLING REPORT

PULLED			EQUIPMENT	RUN		
JTS.	FT.	DESCRIPTION		JTS.	FT.	DESCRIPTION
		2" x 16' 8 Round	ANCHOR			
		2" x 1.10'	PERF. Seat nip			
			WORKING BARREL			
			HOLD DOWN			
104		2" 8 Round	TUBING			
1	8	2" x 8' 8 Round	TUBING SUBS			
			STANDING VALVE			
		1" x 6'	TRAVELING VALVE			
		2" x 1 1/2" x 12'	Gas anchor			
			PUMP			
			RODS			
131	3275	3/4" x 25' Sucker	RODS			
4	20	3/4" x 6' x 6' x 6' x 2'	ROD SUBS			
		1 1/2" x 16'	POLISH ROD			
		1 1/2" x 6'	LINER			

RECEIVED
STATE CORPORATION COMMISSION
MAR 16 1983
CONSERVATION DIVISION
Wichita, Kansas

Unit, Operator & Crew of	2 Men	Hrs. 29	Per Hour. \$96.00	Amount	\$2784.00
Materials and Equipment Used	Power tubing tongs 1 trip @ \$20.00 per trip				20.00
		2 trips @ \$30.00 per trip			60.00
					\$2864.00
4 1/2" slips @ \$85.00 per job					85.00
4 1/2" elevators @ \$75.00 per job					75.00
Dump bailer @ \$75.00 per job					75.00
10 dump bailer glasses @ \$2.00 per glass					20.00
3% state and 1% Barton county sales tax					\$3119.00
					124.76
Solvent and thread dope (used on casing)					\$3243.76
					30.00
				TOTAL:	\$3273.76

Cardwell KB-150 Unit #11 29 hrs. @ \$55.00
 Unit Operator 29 hrs. @ \$15.00
 2 Floor Hands 58 hrs. @ \$13.00

D. S. & W. Well Servicing, Inc.

Date Work Commenced 02-22-83 Date Work Completed 02-24-83

By Urban Oberle