


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Barton County. Sec. 17 Twp. 16 Rge. (E) 12 (W)  
Location as "NE/CNW/SW" or footage from lines NE 1/4 SE 1/4 SE 1/4  
Lease Owner Franco Central Oil Company  
Lease Name Kultgen "F" Well No. 1  
Office Address 512 Fourth National Bank Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 1-28-19 55  
Application for plugging filed 1-28-19 55  
Application for plugging approved 1-28-19 55  
Plugging commenced 1-28-19 55  
Plugging completed 1-28-19 55  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Warren H. Horner  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3388 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	353'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pumped mud to 300' of top, placed plug with 1/2 Sx hulls on top of plug, ran 20 Sx Portland Cement on top of plug. 2nd plug set at 40' w/1/2 Sx hulls on top of plug, ran 10 Sx Portland Cement on top of plug to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lewis Drilling Company  
Address 607 Union National Bank Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
L. L. Bailey (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. L. Bailey  
607 Union National Bank Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 4th day of February, 19 55

My commission expires August 20, 1956

Arthur P. Derrington  
Notary Public.

**PLUGGING**  
FILE REC 17 T 16 R 12W  
BOOK PAGE 94 LINE 29

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 28 1955  
CONSERVATION DIVISION  
2-8-55

15-009-05942-00-00  
**WELL LOG**

COMPANY **Franco Central Oil Company**

SEC. 17 T. 16 R. 12W

FARM **Kultgen "F"** NO. 1

LOC. **NE $\frac{1}{4}$  SE $\frac{1}{4}$  SE $\frac{1}{4}$**

TOTAL DEPTH **3388'**


COUNTY **Barton**

COMM. **1-21-55**

COMP. **1-28-55**

KANSAS

SHOT OR TREATED



CONTRACTOR **Lewis Drilling Company**

ISSUED

CASING

20	10	
15	X 8-5/8"	353'
12	6	
13	5	

ELEVATION **1915 RB**

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

0 ~	353	Surface clay & shale
353 ~	540	Shale
540 ~	570	Red Bed
570 ~	825	Red Bed & Shale
825 ~	1860	Shale & Shells
1860 ~	3200	Shale & Lime
3200 ~	3280	Lime
3280 ~	3388	Lime & Shale
3388	T.D.	

GEOLOGIC TOPS

Heebner	2983'
Brown Lime	3071'
Lansing	3083'
Conglomerate	3361'

State of KANSAS }  
County of SEDGWICK } SS:

I, L. L. Bailey of the Lewis Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the Kultgen "F" #1 well.

*L. L. Bailey*

Subscribed and sworn to before me this 4th day of February 19 55

My Commission Expires: August 20, 1956

**PLUGGING**  
*Robert P. Harrington*  
 NOTARY PUBLIC

FILE SEC 17 T 16 R 12W  
BOOK PAGE 94 LINE 29

RECEIVED  
 STATE GEOLOGICAL COMMISSION  
 FEB - 1955  
 MINERAL RESOURCES DIVISION  
 Topeka, Kansas