

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-009-23,350-00-00

LEASE NAME Kultgen

WELL NUMBER 1

SPOT LOCATION SW NW NE

SEC. 17 TWP. 16 RGE. 12 (E) OR (W)

COUNTY Barton

DATE WELL COMPLETED 11-14-83

PLUGGING COMMENCED 11-14-83

PLUGGING COMPLETED 11-14-83

TYPE OR PRINT
PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

LEASE OPERATOR Canaday Oil Corporation

ADDRESS 710 Petroleum Bldg. Wichita, KS 67202

PHONE # (316) 263-3021 OPERATORS LICENSE NO. 5303

CHARACTER OF WELL D&A
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? David Wann
to be filed

IS ACC-1 FILED? by operator IF NOT, IS WELL LOG ATTACHED? yes

PRODUCING FORMATION _____ DEPTH TO TOP _____ BOTTOM T.D. 3365

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS _____ CASING RECORD _____

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET.

Bottom Plug: @ 850' w/40 sacks 50/50 pozmix, 4% gel 3% cc. thru drill pipe

Next Plug: @ 390' w/80 " " " " " " " "

Top Plug: @ 40' w/bridged plug & 10 sacks cement

10 sacks cement in Rat Hole

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Lobo Drilling Co. LICENSE No. _____
ADDRESS Box 877 Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, SS.

Ervin Neighbors (EMPLOYEE OF OPERATOR) OR
(OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT
I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND
THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND
CORRECT, SO HELP ME GOD.

(SIGNATURE) Ervin Neighbors

(ADDRESS) Box 877 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO BEFORE ME THIS 17 DAY OF November, 1983

Dorothy M. Hoque
NOTARY PUBLIC

MY COMMISSION EXPIRES: 4-29-86

RECEIVED
STATE CORPORATION COMMISSION
NOV 21 1983
CONSERVATION DIVISION
Wichita, Kansas

FORM CP-4
REVISED 06-83

15-009-23350-00-00

DRILLER'S WELL LOG

DATE COMMENCED: November 8, 1983
DATE COMPLETED: November 14, 1983

Canaday Oil Corporation
KULITGEN #1
SW NW NE
Sec. 17, T16S, R12W
Barton County, Ks.

0 - 804' Surface Soil, Post Rock, Red Clay
804 - 832' Anhydrite
832 - 2676' Lime & Shale
2676 - 2954' Lime
2954 - 2959' Shale
2959 - 3058' Lime & Shale
3058 - 3276' Lime
3276 - 3365' Sand
3365' RTD

ELEVATION: 1897 K.B.

FORMATION DATA

Anhydrite .804'
Topeka 2676'
Heebner 2954'
Lansing 3058'
Quartz Sand 3276'
RTD 3365'

Surface Pipe: Set new 8-5/8"
23# pipe @812' w/400 sacks
60/40 pozmix, 2% gel 3% cc.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

Ervin Neighbors of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Ervin Neighbors

Subscribed and sworn to before me this 17 day of November 1983.

My Comm. Expires:

4-29-86

Dorothy M Hague
Notary Public

RECEIVED
STATE CORPORATION COMMISSION
NOV 21 1983
CONSERVATION DIVISION
Wichita, Kansas